



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION

NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY, FLORIDA
PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208
T (786) 315-2590 F (786) 315-2599

www.miamidade.gov/economy

PGT Industries, Inc.
1070 Technology Drive
North Venice, Fl. 34275

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami-Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/ or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code. This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series "FD-555" Outswing PVC French Door w/ & w/o Sidelite and Transom – L.M.I.

APPROVAL DOCUMENT: Drawing No. MD-555.1, titled "Vinyl French Door and SLT/ TR", sheets 1 through 12 of 12, dated 05/07/13 with revision A dated 03/18/15, prepared by manufacturer, signed and sealed by Anthony Lynn Miller, P.E., bearing the Miami-Dade County Product Control Section Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/ or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises NOA No. 13-0815.03 and consists of this page 1 and evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by Manuel Perez, P. E.



MP
7/7/15

NOA No. 15-0409.03
Expiration Date: January 23, 2019
Approval Date: July 02, 2015
Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.
(Submitted under previous NOA No. 13-0815.03)
2. Drawing No. **MD-555.1**, titled "Vinyl French Door and SLT/TR", sheets 1 through 12 of 12, dated 05/07/13, with revision A dated 03/18/15, prepared by manufacturer, signed and sealed by Anthony Lynn Miller, P.E.

B. TESTS

1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
along with marked-up drawings and installation diagram of an outswing PVC French door, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **FTL-7370**, dated 05/23/13, signed and sealed by Jorge A. Naya, Jr., P.E.
(Submitted under previous NOA No. 13-0815.03)
2. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
2) Large Missile Impact Test per FBC, TAS 201-94
3) Cyclic Wind Pressure Loading per FBC, TAS 203-94
along with marked-up drawings and installation diagram of an outswing Rigid PVC French door, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **FTL-7371**, dated 05/25/13, signed and sealed by Jorge A. Naya, Jr., P.E.
(Submitted under previous NOA No. 13-0815.03)
3. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
along with marked-up drawings and installation diagram of a PVC fixed window, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **FTL-7338**, dated 05/25/13, signed and sealed by Jorge A. Naya, Jr., P.E.
(Submitted under previous NOA No. 13-0815.03)
4. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
2) Large Missile Impact Test per FBC, TAS 201-94
3) Cyclic Wind Pressure Loading per FBC, TAS 203-94
along with marked-up drawings and installation diagram of a Rigid PVC fixed window, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **FTL-7339**, dated 05/23/13, signed and sealed by Jorge A. Naya, Jr., P.E.
(Submitted under previous NOA No. 13-0815.03)



Manuel Perez, P.E.
Product Control Examiner
NOA No. 15-0409.03

Expiration Date: January 23, 2019
Approval Date: July 02, 2015

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

C. CALCULATIONS

1. Anchor verification calculations and structural analysis, complying with **FBC 5th Edition (2014)**, dated 03/30/15, prepared by manufacturer, signed and sealed by Anthony Lynn Miller, P.E.
2. Glazing complies with **ASTM E1300-04/09**

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER).

E. MATERIAL CERTIFICATIONS

1. Notice of Acceptance No. **14-0916.10** issued to **Kuraray America, Inc.** for their "**Kuraray Butacite® PVB Glass Interlayer**" dated 04/25/15, expiring on 12/11/16.
2. Notice of Acceptance No. **14-0916.11** issued to **Kuraray America, Inc.** for their "**Kuraray SentryGlas® (Clear and White) Glass Interlayers**" dated 06/25/15, expiring on 07/04/18.
3. Notice of Acceptance No. **14-0820.11** issued to Vision Extrusions Limited for their "**White Rigid PVC Exterior Extrusions for Windows and Doors**", dated 11/06/14, expiring on 09/30/19.
4. Notice of Acceptance No. **14-0820.12** issued to Vision Extrusions Limited for their "**Brown Coated (Painted or Laminated) White Rigid PVC Exterior Extrusions for Windows and Doors**", dated 11/06/14, expiring on 09/30/19.
5. Notice of Acceptance No. **13-1121.01** issued to Vision Extrusions Limited for their series "**VE 2000 Tan 202 and lighter shades (Non-White) Rigid Cellular PVC Exterior Extrusions for Windows and Doors**" dated 01/23/14, expiring on 01/23/19.
6. Notice of Acceptance No. **13-1121.02** issued to Vision Extrusions Limited for their series "**White Rigid Cellular PVC Exterior Extrusions for Windows and Doors**" dated 01/23/14, expiring on 01/23/19.
7. Notice of Acceptance No. **11-0902.10** issued to Vision Extrusions Limited for their series "**VE 1000 Tan 202 (Non-White) Rigid PVC Exterior Extrusions for Windows and Doors**" dated 12/29/11, expiring on 12/29/16.
8. Quanex Part **Super Spacer Standard** complying with ASTM C518 Thermal Conductivity 0.881 BTU-in/ hr.-ft²-°F, ASTM F 1249 WVTR-Pass, ASTM D3985 Oxygen-Pass, ASTM E 2190 I.G. Durability-No Fog-Pass.
(Submitted under previous NOA No. 13-0815.03)
9. Quanex Part **Duraseal** complying with ASTM C518 Thermal Conductivity 2.22 BTU-in/ hr.-ft²-°F, ASTM F 1249 WVTR-Pass, ASTM D 1434 Argon Permeance-Pass, ASTM E 2189 I.G. Durability-No Fog, ASTM E 546 Dew Point Development -20°F in 48 hrs.
(Submitted under previous NOA No. 13-0815.03)


Manuel Perez, P.E.
Product Control Examiner
NOA No. 15-0409.03

Expiration Date: January 23, 2019
Approval Date: July 02, 2015

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

E. MATERIAL CERTIFICATIONS (CONTINUED)

10. Vision Extrusions, Ltd. Parts complying with PVC-AAMA 303-13.
(Submitted under previous NOA No. 13-0815.03)
11. PVC-AAMA 303-13, Voluntary Specification for Rigid Polyvinyl Chloride (PVC) Exterior Profiles for Vision Extrusions, Ltd.-VEX-1 by AAMA Fenestration Exterior Profile Certification Program.
(Submitted under previous NOA No. 13-0815.03)

F. STATEMENTS

1. Statement letter of conformance to and of complying with **FBC 5th Edition (2014)**, dated 03/30/15, issued by manufacturer, signed and sealed by A. Lynn Miller, P.E.
2. Statement letter of no financial interest and of independent, issued by manufacture, dated 03/30/15, signed and sealed by Anthony Lynn Miller, P.E.
3. Laboratory compliance letter for Test Reports No. **FTL-7370, FTL-7371, FTL-7338** and **FTL-7339**, all issued by Fenestration Testing Laboratory, Inc., dated 05/23/13 and 05/25/13, all signed and sealed by Jorge A. Naya, Jr., P.E.
(Submitted under previous NOA No. 13-0815.03)

G. OTHERS

1. Notice of Acceptance No. **13-0815.03**, issued to PGT Industries, Inc. for their Series "FD-555 Vinyl" Outswing VE 2000 Tan 202 lighter shades (Non-White and White) Rigid Cellular PVC Door w/ Sidelites and w/ Transoms - L.M.I., approved on 01/23/14 and expiring on 01/23/19.

Manuel Perez, P.E.
Product Control Examiner
NOA No. 15-0409.03
Expiration Date: January 23, 2019
Approval Date: July 02, 2015

GENERAL NOTES: SERIES FD-5555,
IMPACT-RESISTANT, VINYL, REINFORCED, OUTSWING
FRENCH DOOR & SIDELITE/TRANSOM (SLT/TR)

DESIGN PRESSURE RATING	IMPACT RATING
VARIES, SEE SHEETS 4 & 5	RATED FOR LARGE & SMALL MISSILE IMPACT RESISTANCE

1) THIS PRODUCT HAS BEEN DESIGNED & TESTED TO COMPLY WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE, INCLUDING THE HIGH VELOCITY HURRICANE ZONE (HVHZ).

2) SHUTTERS ARE NOT REQUIRED WHEN USED IN WIND-BORNE DEBRIS REGIONS.

3) FOR MASONRY APPLICATIONS IN MIAMI-DADE COUNTY, USE ONLY MIAMI-DADE COUNTY APPROVED MASONRY ANCHORS. MATERIALS USED FOR ANCHOR EVALUATIONS WERE SOUTHERN PINE, ASTM C90 CONCRETE MASONRY UNITS (CMU'S) OF NORMAL WEIGHT AND OF COMPRESSIVE STRENGTH OF MIN. 1.9 KSI) AND CONCRETE WITH MIN. KSI PER ANCHOR TYPE.

4) MASONRY ANCHORS MAY BE USED INTO WOOD AS PER TABLE 1, THIS SHEET. ALL WOOD BUCKS LESS THAN 1-1/2" THICK ARE TO BE CONSIDERED 1X INSTALLATIONS. 1X WOOD BUCKS ARE OPTIONAL IF UNIT IS INSTALLED DIRECTLY TO SUBSTRATE. WOOD BUCKS DEPICTED AS 2X ARE 1-1/2" THICK OR GREATER. 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED TO PROPERLY TRANSFER LOADS TO THE STRUCTURE. WOOD BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD.

5) IF SILL IS TIGHT TO SUBSTRATE, GROUT IS NOT REQUIRED. IF USED, NON-SHRINK, NON-METALLIC GROUT AT 3.4 KSI MIN. PER ASTM C1107, (DONE BY OTHERS). MAX. 1/4" SHIM SPACE FOR GROUT WHICH MUST FULLY SUPPORT THE ENTIRE LENGTH OF THE SILL THAT IS NOT TIGHT TO THE SUBSTRATE, AND TRANSFER SHEAR LOAD TO SUBSTRATE. IF SUBSTRATE IS WOOD, 30# FELT PAPER OR MASTIC IS REQUIRED BETWEEN THE GROUT AND WOOD SUBSTRATE, OR AS APPROVED BY THE AUTHORITY HAVING JURISDICTION, COMPLYING WITH THE FBC.

6) ANCHOR EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO. USE ANCHORS OF SUFFICIENT LENGTH TO ACHIEVE THE EMBEDMENT SHOWN ON TABLE 1, THIS SHEET. NARROW JOINT SEALANT IS USED ON ALL FOUR CORNERS OF THE FRAME. EXTERIOR INSTALLATION ANCHORS SHOULD BE SEALED. OVERALL SEALING/FLASHING STRATEGY FOR WATER RESISTANCE OF INSTALLATION SHALL BE DONE BY OTHERS AND IS BEYOND THE SCOPE OF THESE INSTRUCTIONS.

7) MAX. 1/4" SHIMS ARE REQUIRED AT EACH ANCHOR LOCATION WHERE THE PRODUCT IS NOT FLUSH TO THE SUBSTRATE. USE SHIMS CAPABLE OF TRANSFERRING APPLIED LOADS. WOOD BUCKS, BY OTHERS, MUST BE SUFFICIENTLY ANCHORED TO RESIST LOADS IMPOSED ON THEM BY THE DOOR, SIDELITE OR TRANSOM.

8) DESIGN PRESSURES:
A. NEGATIVE DESIGN LOADS BASED ON STRUCTURAL TEST PRESSURE, FRAME ANALYSIS AND GLASS PER ASTM E1300.
B. POSITIVE DESIGN LOADS BASED ON WATER TEST PRESSURE, STRUCTURAL TEST PRESSURE, FRAME ANALYSIS AND GLASS PER ASTM E1300.

9) THE ANCHORAGE METHODS SHOWN HAVE BEEN DESIGNED TO RESIST THE WINDLOADS CORRESPONDING TO THE REQUIRED DESIGN PRESSURE. THE 33-1/3% STRESS INCREASE HAS NOT BEEN USED IN THE DESIGN OF THIS PRODUCT. THE 1.6 LOAD DURATION FACTOR WAS USED FOR THE EVALUATION OF ANCHORS INTO WOOD. ANCHORS THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF THE FLORIDA BUILDING CODE (INCLUDING ADOPTED STANDARDS) FOR CORROSION RESISTANCE.

10) ALL RIGID PVC AND RIGID CELLULAR CPVC MANUFACTURED BY VISION EXTRUSIONS, LTD. HAS BEEN TESTED TO COMPLY WITH THE FLORIDA BUILDING CODE FOR PLASTICS.

11) SIZES MUST BE VERIFIED FOR COMPLIANCE WITH EGRESS REQUIREMENTS PER THE FLORIDA BUILDING CODE.

12) REFERENCES:
TEST REPORTS: FTL-7339 & 7371
NOA'S: ELCO ULTRAACON NOA; ELCO CRETEFLEX NOA; ELCO AGGRE-GATOR NOA;
VISION EXTRUSIONS, LTD. WHITE RIGID, VE 1000 TAN 202 (NON-WHITE) RIGID & BROWN-COATED (PAINTED OR LAMINATED) RIGID PVC NOA'S, VISION EXTRUSIONS LTD. WHITE & VE 2000 TAN (NON-WHITE) RIGID CELLULAR PVC NOA'S, ANSI/AF&PA NDS FOR WOOD CONSTRUCTION AND ADM ALUMINUM DESIGN MANUAL.

13) THE 5555 SERIES IS ALSO KNOWN AS THE 555 SERIES.

14) INTERLAYERS MAY BE MANUFACTURED BY E.I. DUPONT DENEMOURS & CO., INC. OR KURARAY AMERICA, INC.

TABLE 1:

Group	Anchor	Substrate	Min. Edge Distance	Min. Embedment
A	3/16" Elco Ultracon	UngROUTED CMU, (ASTM C-90)	1"	1-1/4"
		UngROUTED CMU, (ASTM C-90)	2-1/2"	1-1/4"
B	#10 Steel SMS (G5) #10 410 S.S. SMS #10 18-8 S.S. SMS	P.T. Southern Pine (SG=0.55)	1/2"	1-3/8"
		Aluminum, 6063-T5*	5/16"	0.063"
		Steel, A36*	5/16"	0.063"
		Steel Stud, A653 Gr. 33*	5/16"	0.063"
	3/16" Elco Ultracon	P.T. Southern Pine (SG=0.55)	1/2"	1-3/8"
		Grouted CMU, (ASTM C-90)	2-1/2"	2-1/4"
		Concrete (min. 2.85 ksi)	1"	1-3/8"
	1/4" Elco Ultracon	UngROUTED CMU, (ASTM C-90)	2-1/2"	1-1/4"
		P.T. Southern Pine (SG=0.55)	9/16"	1-3/8"
		Aluminum, 6063-T5*	3/8"	0.071"
C	#12 Steel SMS (G5) #12 410 S.S. SMS #12 18-8 S.S. SMS	Steel, A36*	3/8"	0.071"
		Steel Stud, A653 Gr. 33*	3/8"	0.071" (14 Ga)
		P.T. Southern Pine (SG=0.55)	1"	1-3/8"
		Grouted CMU, (ASTM C-90)	2-1/2"	1-3/4"
	1/4" Elco Ultracon	Concrete (min. 2.85 ksi)	1"	1-3/8"
		Concrete (min. 3.35 ksi)	1"	1-3/4"
		UngROUTED CMU, (ASTM C-90)	2-1/2"	1-1/4"
	1/4" Elco 410 S.S. CreteFlex	P.T. Southern Pine (SG=0.55)	1"	1-3/8"
		Concrete (min. 3.27 ksi)	1-1/2"	1-3/8"
		UngROUTED CMU, (ASTM C-90)	4"	1-1/4"
	1/4" Elco 18-8 S.S. Aggre-Gator	Concrete (min. 2.85 ksi)	2-1/2"	1-3/8"
		Concrete (min. 3.35 ksi)	2-1/2"	1-3/4"
D	1/4" Elco Ultracon	Concrete (min. 2.85 ksi)	2-1/2"	1-3/8"
	1/4" Elco410 S.S. CreteFlex	Concrete (min. 3.35 ksi)	2-1/2"	1-3/4"

* MIN. OF 3 THREADS BEYOND THE METAL SUBSTRATE.

TABLE 2:

Type #	Description	Where Used:
1	1-3/16" Lami. IG (1/8" T - 11/16" Air - 1/8" An - .090" PVB - 1/8" An)	Door
2	1-3/16" Lami. IG (3/16" T - 5/8" Air - 1/8" An - .090" PVB - 1/8" An)	
3	1-3/16" Lami. IG (1/8" T - 9/16" Air - 3/16" An - .090" SG - 3/16" An)	Sidelite & Transom (SLT/TR)
4	1-3/16" Lami. IG (3/16" T - 1/2" Air - 3/16" An - .090" SG - 3/16" An)	
5	1-3/16" Lami. IG (1/8" T - 9/16" Air - 3/16" An - .090" PVB - 3/16" An)	
6	1-3/16" Lami. IG (3/16" T - 1/2" Air - 3/16" An - .090" PVB - 3/16" An)	

PVB = POLYVINYL BUTACITE
SG = SENTRYGLAS® INTERLAYER
SEE TABLE 11 FOR SPACER INFORMATION

GUIDE TO SHEETS:

GENERAL NOTES.....	1
ELEVATIONS.....	2
GLAZING DETAILS.....	3
DESIGN PRESSURES.....	4-5
SIDELITE/TRANSOM ANCHORS.....	4-6
INSTALLATION.....	7-9
EXTRUSION PROFILES.....	10
PARTS LIST.....	11-12
CORNER DETAILS.....	11
HARDWARE DETAILS.....	12

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0409.03
Expiration Date 07/23/2019
By *Manuel Perez*
Miami Dade Product Control

Rev A A) UPDATED ANCHOR TABLE,
Rev B CHANGED SERIES # - JR - 03/18/15
Rev C

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
(941) 480-1600


5/7/13
Date
J ROSOWSKI
By
MD-555.1
Rev
A

1 OF 12
DWG
Sheet
NTS
Scale
FD-5555
Series Desc. Title


GENERAL NOTES

ANTHONY LYNN MILLER
LICENSE
No. 58705
6/16/15
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
P.E.# 58705


EXAMPLE CONFIGURATIONS




TYP. DOOR SLAB




X



XX




OIX (SHOWN) OR XIO
(WIDE STILES AND WIDE RAILS
SHOWN ON SIDELITES)




OIXIO
(NARROW STILES AND WIDE
RAILS SHOWN ON SIDELITES)


DETAIL
SHEET #




OIXXIO
(WIDE STILES AND WIDE
RAILS SHOWN ON SIDELITES)




SINGLE O
(WIDE STILES AND WIDE
RAILS SHOWN ON SIDELITES)




SINGLE O
(NARROW STILES AND NARROW
RAILS SHOWN ON SIDELITES)



OIO (ADDITIONAL MULLED
LITES ALLOWED)
(WIDE STILES AND NARROW
RAILS SHOWN ON SIDELITES)



O/O WITH
HORIZONTAL
MULLION
(WIDE STILES AND
WIDE RAILS SHOWN
ON SIDELITE &
TRANSOM)





O/X WITH
HORIZONTAL
MULLION
(NARROW STILES
AND NARROW
RAILS SHOWN ON
TRANSOM)

- NOTES:
- 1) SINGLE DOORS MAY BE LEFT OR RIGHT-HANDED.
 - 2) MULLIONS SHOWN ARE STANDARD 1" FRENCH DOOR MULLIONS PER THIS NOA.
 - 3) MULLED CONFIGURATIONS NOT SHOWN MAY BE POSSIBLE USING OTHER MULLION TYPES, SEE SEPARATE NOA.
 - 4) FRENCH DOOR MULLION IS LIMITED TO 96" IN VERTICAL APPLICATIONS AND 40" IN HORIZONTAL APPLICATIONS.
 - 5) NARROW OR WIDE STILES AND RAILS MAY BE MIXED WITHIN THE SAME SLT/TR OR MULLED ASSEMBLY.
 - 6) ADDITIONAL CONFIGURATIONS USING THE 1" FRENCH DOOR MULLION ARE POSSIBLE. USE THE ABOVE DRAWINGS AS A REFERENCE FOR SIZE LIMITATIONS.


PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0409.03
Expiration Date 01/23/2019
By *Manuel Perez*
Miami Dade Product Control

Rev A
Rev B
Rev C
A) NO CHANGES THIS SHEET -
JR - 03/18/15


										1070 TECHNOLOGY DRIVE N. VENICE, FL 34275 P.O. BOX 1529 NOKOMIS, FL 34274 (941)-480-1600													
CERT. OF AUTH. #29296										VINYL FRENCH DOOR AND SLT/TR										Date		5/7/13	
EXAMPLE CONFIGURATIONS										Drawn By		J ROSOWSKI											
Series		FD-5555		Scale		NTS		Sheet		2 OF 12		DWG No.		MD-555.1		Rev		A					



DOOR GLAZING DETAILS




GLASS TYPE 1




GLASS TYPE 2

PVB = POLYVINYL BUTACITE
SG = SENTRYGLAS® INTERLAYER


SIDELITE & TRANSOM GLAZING DETAILS




GLASS TYPE 3
TYP. WIDE FRAME GLAZING
DETAIL, NARROW FRAME SIMILAR



GLASS TYPE 5
TYP. NARROW FRAME GLAZING
DETAIL, WIDE FRAME SIMILAR.




GLASS TYPE 4
TYP. NARROW FRAME GLAZING
DETAIL, WIDE FRAME SIMILAR.




GLASS TYPE 6
TYP. WIDE FRAME GLAZING
DETAIL, NARROW FRAME SIMILAR


PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0409.03
Expiration Date 07/23/2019
By *Manuel Serr*
Miami Dade Product Control

Rev A
Rev B
Rev C
A) NO CHANGES THIS SHEET -
JR - 03/18/15

1070 TECHNOLOGY DRIVE N. VENICE, FL 34275 P.O. BOX 1529 NOKOMIS, FL 34274 (941)-480-1600	Date	5/7/13	J ROSOWSKI	Rev.	A
		By			MD-555.1
		No.			
		DWG			
	Sheet	3 OF 12	GLAZING DETAILS	Scale	NTS
		FD-5555			



SINGLE DOOR INSTALLATION (X)




X

TABLE 3:

DOOR DESIGN PRESSURE	
+/-50.0 PSF	Glass Type 1
+/-70.0 PSF	Glass Type 2

DOUBLE DOOR INSTALLATION (XX)



XX, (USING ASTRAGAL)

TABLE 4:

XX Door: Astragal Cluster Anchors Required @ Head & Sill									
Door Height (in)	Door Width (in)								
	48	60	72	76	Anchor Group B-D	Anchor Group B	Anchor Group C&D	Anchor Group C	
80	4	4	4	5	4	5	4	4	
96	4	5	4	6	4	6	5	4	

4" O.C. MIN., SEE TABLE 4, THIS SHEET, FOR QUANTITY, SEE TABLE 1, SHEET 1 FOR TYPE

SEE NOTE 1

SIDELITE-TO-SIDELITE MULLION INSTALLATION (O/O, O/O/O, ETC.)





TABLE 5:

VERTICAL MULLION DESIGN PRESSURE
+/-70.0 PSF



SIDELITE-TO-DOOR MULLION INSTALLATION (X/O, O/X, X/X, O/X/O, X/O/X, O/XX/O, ETC)






TABLE 6:

Anchors Required for a Vertical Mullion (each mullion end)													
Door or Sidelite/Transom Width (in)	Mullion Height (in)	Door or Sidelite/Transom Width (in)											
		12	24	32	36-3/4	40	Anchor Group B-D	Anchor Group B&C	Anchor Group D	Anchor Group B	Anchor Group C	Anchor Group D	Anchor Group B
Door	80	N/A	2	1	2	2	1	3	2	1	N/A	N/A	N/A
SLT/TR	80	1	2	1	2	2	1	3	2	1	3	2	1
Door	96	N/A	2	1	3	2	1	3	3	2	N/A	N/A	N/A
SLT/TR	96	1	2	1	3	2	1	3	3	2	3	3	2

FOR "O/XX/O" AND SIMILAR CONFIGURATIONS CONTAINING A DOUBLE DOOR (XX), USE ONLY HALF OF THE FRAME WIDTH OF THE DOUBLE DOOR WHEN USING THIS TABLE.

TRANSOM-TO-DOOR (X/O) OR TRANSOM-TO-SIDELITE (O/O) MULLION ATTACHMENT & INSTALLATION

ATTACH DOORS, SIDELITES & TRANSOMS TO THE MULLION AS PER THE INSTRUCTION OF THE INDIVIDUAL PRODUCT



1" MULLION
HORIZONTAL MULLION APPLICATIONS ALWAYS REQUIRE TWO (2) ANCHORS (TYPE A-D) AT EACH MULLION END.

40" MAX. MULLION LENGTH IN HORIZONTAL APPLICATIONS. TRANSOMS WIDER THAN 40" WILL REQUIRE ADDITIONAL STRUCTURE OR DADE-APPROVED MULLION BETWEEN TRANSOM AND DOOR/SIDELITE.

TABLE 7:

HORIZONTAL MULLION DESIGN PRESSURE
+/-70.0 PSF

PRODUCT REVISED as complying with the Florida Building Code Acceptance No. 15-0409.03 Expiration Date 02/23/2019 By *M. Miller* /Miami/Dade Product Control

Rev A NO CHANGES THIS SHEET - JR - 03/18/15
Rev B
Rev C

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
(941)-480-1600

CERT. OF AUTH. #29296

VINYL FRENCH DOOR AND SLT/TR

DESIGN PRESSURE 1

FD-5555

4 OF 12

MD-555.1

J ROSOWSKI

5/7/13

Rev. A

ANTHONY LYNN MILLER
LICENSE
No. 58705
6/16/15
STATE OF FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
P.E.# 58705

INSTRUCTIONS:

- 1) DOOR HINGE JAMBS OF ALL HEIGHTS TO ALWAYS BE ANCHORED WITH SIX ANCHORS. SEE TABLE 1, SHEET 1, FOR ALL APPROVED ANCHORS. FOUR OF THE SIX ANCHORS MUST BE INSTALLED THROUGH THE HINGES, ONE AT EACH HINGE LOCATION (RECOMMENDED #10 FLATHEAD SMS OR 3/16" FLATHEAD ULTRACON FOR EACH HINGE ANCHOR).
- 2) FOR A MULLED UNIT, DETERMINE THE DESIGN PRESSURE OF EACH COMPONENT IN THAT CONFIGURATION. FOR EXAMPLE, ON AN "X/O" CONFIGURATION, THE DP FOR THE DOOR, THE MULLION AND THE SIDELITE MUST EACH BE DETERMINED. THE LOWEST DP APPLIES TO THE ENTIRE ASSEMBLY.

NOTES:

- 1) SINGLE DOOR MAY BE LEFT OR RIGHT-HANDED.
- 2) MULLIONS SHOWN ARE STANDARD 1" FRENCH DOOR MULLIONS.
- 3) MULLED CONFIGURATIONS NOT SHOWN MAY BE POSSIBLE USING OTHER MULLION TYPES, SEE SEPARATE NOA. THE LOWEST COMPONENT DP IS TO BE THE OVERALL ASSEMBLY DP.
- 4) FRENCH DOOR MULLION IS LIMITED TO 96" IN VERTICAL APPLICATIONS AND 40" IN HORIZONTAL APPLICATIONS.
- 5) NARROW OR WIDE STILES AND RAILS MAY BE MIXED WITHIN THE SAME SIDELITE/TRANSOM OR MULLED ASSEMBLY.
- 6) FOR SIZES NOT SHOWN, ROUND UP TO THE NEXT AVAILABLE SHORT OR LONG DIMENSION.

TABLE 8:

TABLE 8:

		Sidelite/Transom Design Pressure (+/-, psf) for Glass Types 3 & 4																
		Long Side (in)																
		63-3/16	66-5/8	68	70	72	76	78	82	84	88	92	96	98	104	108	111	
Short Side (in)	24	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	
	28	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	
	32	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	
	36	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	
	38-3/4	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	
	40	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	
	42	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-69.6	+/-68.5		
	44	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-69.6	+/-68.6	+/-67.7	+/-67.3				
	46	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-69.4	+/-68.7	+/-67.6	+/-66.5	+/-65.6					
	48	+/-70	+/-70	+/-70	+/-70	+/-70	+/-69.9	+/-69.1	+/-67.6	+/-67	+/-65.8	+/-64.7						
	50	+/-70	+/-70	+/-70	+/-70	+/-70	+/-68.4	+/-67.6	+/-66	+/-65.4	+/-64.1							
	52	+/-70	+/-70	+/-70	+/-70	+/-69.1	+/-67.1	+/-66.2	+/-64.6	+/-63.9								
	54	+/-70	+/-70	+/-70	+/-69.2	+/-68	+/-65.9	+/-65	+/-63.4									
	56	+/-70	+/-70	+/-69.7	+/-68.3	+/-67.1	+/-64.9	+/-63.9										
	58	+/-70	+/-70	+/-69	+/-67.6	+/-66.3	+/-64											
	60	+/-70	+/-69.6	+/-68.5	+/-67	+/-65.6												
	62	+/-70	+/-69.2	+/-68	+/-66.5													
	63-3/16	+/-70	+/-69.1	+/-67.9	+/-66.2													
66-5/8	+/-69.1	+/-68.9																

SIDELITE/TRANSOM INSTALLATION (O)




TABLE 9:

TABLE 9:

		Sidelite/Transom Design Pressure, psf for Glass Types 5 & 6															
		Long Side (in)															
		63-3/16	66-5/8	68	70	72	76	78	82	84	88	92	96	98	104	108	111
Short Side (in)	24	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70
	28	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70
	32	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70
	36	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70
	38-3/4	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-69.9	+/-69	+/-68.3	+/-67.9			
	40	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-70	+/-69.8	+/-69.3	+/-68.3	+/-67.4	+/-66.7	+/-66.3			
	42	+/-70	+/-70	+/-70	+/-70	+/-70	+/-69.5	+/-68.8	+/-67.6	+/-67	+/-66	+/-65.1					
	44	+/-70	+/-70	+/-70	+/-70	+/-69.1	+/-67.5	+/-66.8	+/-65.6	+/-65	+/-64						
	46	+/-70	+/-70	+/-69.4	+/-68.4	+/-67.4	+/-65.8	+/-65.1	+/-63.8	+/-63.2							
	48	+/-70	+/-68.8	+/-68	+/-66.9	+/-66	+/-64.3	+/-63.5	+/-62.2								
	50	+/-69.9	+/-67.6	+/-66.8	+/-65.7	+/-64.7	+/-62.9	+/-62.1									
	52	+/-69	+/-66.6	+/-65.7	+/-64.6	+/-63.6	+/-61.7										
	54	+/-68.3	+/-65.7	+/-64.8	+/-63.6	+/-62.6											
	56	+/-67.7	+/-65	+/-64.1	+/-62.8												
	58	+/-67.3	+/-64.5	+/-63.5													
	60	+/-67															
	62	+/-66.9															
63-3/16	+/-66.8																

NOTES:
1) NARROW OR WIDE STILES AND RAILS MAY BE MIXED WITHIN THE SAME SIDELITE/TRANSOM OR MULLED ASSEMBLY.
2) SIDELITE/TRANSOM MAY BE A SINGLE, STAND-ALONE UNIT.
3) FOR SIZES NOT SHOWN, ROUND UP TO THE NEXT AVAILABLE SHORT OR LONG DIMENSION.

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0409.03
Expiration Date 01/23/2019
By *Manuel Sese*
Miami Dade Product Control

Rev C Rev B Rev A
A) CORRECTED TABLE 8 DIM. -
JR - 03/18/15

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
(941)-480-1600

PG
CERT. OF AUTH. #29296

VINYL FRENCH DOOR AND SLT/TR
DESIGN PRESSURE 2

5/7/13
J ROSOWSKI
MD-555.1
5 OF 12
FD-5555
NTS
Scale
Sheet
No.

Rev. A

ANTHONY LYNN MILLER
LICENSE
No. 58705
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
P.E.# 58705

TABLE 10:


			Sidelite/Transom Anchor Quantity																																
			Long Side (in)																																
			63-3/16		66-5/8		68		70		72		76		78		82		84		88		92		96		98		104			108		111	
			Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Group B	Anchor Groups C-D	Anchor Group A	Anchor Groups B-D	Anchor Group A	Anchor Groups B-D
Short Side (in)	24	Short Side	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	
		Long Side	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	5	5	5	5	5	5	5	5	5	5	6	5	5	6	6	6	6	
	28	Short Side	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	
		Long Side	4	4	4	4	4	4	4	4	4	4	5	4	5	4	5	4	5	5	5	5	6	5	6	5	6	5	6	5	5	7	6	7	6
	32	Short Side	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	
		Long Side	4	4	4	4	4	4	4	4	4	5	4	5	4	5	4	6	5	6	5	6	5	6	5	7	5	7	5	5	7	6	8	6	
	36	Short Side	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	
		Long Side	4	4	5	4	5	4	5	4	5	4	5	4	5	4	6	4	6	5	6	5	7	5	7	5	7	5	8	5	5	7	6	8	6
	38-3/4	Short Side	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
		Long Side	4	4	5	4	5	4	5	4	5	4	6	4	6	4	6	4	6	5	7	5	7	5	7	5	8	5	8	5	5	8	6	9	6
	40	Short Side	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
		Long Side	4	4	5	4	5	4	5	4	5	4	6	4	6	4	6	4	6	5	7	5	7	5	8	5	8	5	8	5	5	9	6	9	6
	42	Short Side	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3				
		Long Side	5	4	5	4	5	4	5	4	5	4	6	4	6	4	6	4	7	5	7	5	7	5	8	5	8	5	8	6	5				
	44	Short Side	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3					
		Long Side	5	4	5	4	5	4	5	4	6	4	6	4	6	4	7	4	7	5	7	5	7	5	8	5	8	5							
	46	Short Side	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3						
		Long Side	5	4	5	4	5	4	6	4	6	4	6	4	6	4	7	4	7	5	7	5	7	5	8	5									
	48	Short Side	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3							
		Long Side	5	4	5	4	5	4	6	4	6	4	6	4	6	4	7	4	7	5	7	5	7	5											
50	Short Side	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3									
	Long Side	5	4	5	4	5	4	6	4	6	4	6	4	6	4	7	4	7	5	7	5														
52	Short Side	4	3	4	3	4	3	4	3	4	3	4	3	4	3	4	3	4	3	4	3	4	3	4	3	4									
	Long Side	5	4	5	4	6	4	6	4	6	4	6	4	6	4	7	4	7	5																
54	Short Side	4	3	4	3	4	3	4	3	4	3	4	3	4	3	4	3	4	3																
	Long Side	5	4	5	4	6	4	6	4	6	4	6	4	6	4	7	4																		
56	Short Side	4	3	4	3	4	3	4	3	4	3	4	3	4	3	4	3																		
	Long Side	5	4	6	4	6	4	6	4	6	4	6	4	6	4	6	4																		
58	Short Side	4	3	4	3	4	3	4	3	4	3	4	3																						
	Long Side	5	4	6	4	6	4	6	4	6	4	6	4	6	4																				
60	Short Side	5	4	5	4	5	4	4	4	4	4																								
	Long Side	5	4	6	4	6	4	6	4	6	4																								
62	Short Side	5	4	5	4	5	4	5	4																										
	Long Side	5	4	6	4	6	4	6	4																										
63-3/16	Short Side	5	4	5	4	5	4																												
	Long Side	5	4	6	4	6	4																												
66-5/8	Short Side	6	4	6	4																														
	Long Side	5	4	6	4																														

NOTES:
1) NARROW OR WIDE STILES AND RAILS MAY BE MIXED WITHIN THE SAME SIDELITE/TRANSOM OR MULLED ASSEMBLY.
2) SIDELITE/TRANSOM MAY BE A SINGLE, STAND-ALONE UNIT.
3) FOR SIZES NOT SHOWN, ROUND UP TO THE NEXT AVAILABLE SHORT OR LONG DIMENSION.

PRODUCT REVIEWED
as complying with the Florida
Building Code
Acceptance No. 15-0409.03
Expiration Date 04/23/2019
By *Manuel Perez*
Miami Dade Product Control

Rev A A) NO CHANGES THIS SHEET -
JR - 03/18/15
Rev B
Rev C

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
(941)-480-1600







CERT. OF AUTH. #29296

VINYL FRENCH DOOR AND SLT/TR
SLT/TR ANCHOR QUANTITIES

5/7/13
J ROSOWSKI
MD-555.1
6 OF 12
NTS
FD-5555

Rev
A

ANTHONY LYNN MILLER
LICENSE
No. 58705
6/16/15
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
P.E.# 58705




INSTALLATION NOTES:

- 1) USE ONLY SUBSTRATE-APPROPRIATE ANCHORS LISTED ON TABLE 1, SHEET 1. FOLLOW EMBEDMENT AND EDGE DISTANCE LIMITS. ANY INSTALLATION OPTION SHOWN MAY BE USED ON ANY SIDE OF THE DOOR, SIDELITE OR TRANSOM.
- 2) WOOD BUCKS DEPICTED ON THIS SHEET AS "1X", ARE BUCKS WHOSE TOTAL THICKNESS IS LESS THAN 1-1/2". 1X WOOD BUCKS ARE OPTIONAL IF UNIT CAN BE INSTALLED DIRECTLY TO MASONRY. WOOD BUCKS DEPICTED AS "2X" ARE 1-1/2" THICK OR GREATER. INSTALLATION TO THE SUBSTRATE OF WOOD BUCKS TO BE ENGINEERED BY OTHERS OR AS APPROVED BY THE AUTHORITY HAVING JURISDICTION.
- 3) FOR ATTACHMENT TO METAL: THE STRUCTURAL MEMBER SHALL BE OF A SIZE TO PROVIDE FULL SUPPORT TO THE FRAME OF THE DOOR, SIDELITE OR TRANSOM.
- 4) IF APPLICABLE, LOWEST DESIGN PRESSURE FROM DOOR, SIDELITE, TRANSOM OR MULLION APPLIES TO THE WHOLE SYSTEM.


PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. **15-0409.03**
Expiration Date **03/23/2019**
By *Manuel Perez*
Miami/Dade Product Control



Rev C Rev B Rev A
A) NO CHANGES THIS SHEET -
JR - 03/18/15

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
(941)-480-1600



1070 TECHNOLOGY DRIVE N. VENICE, FL 34275 P.O. BOX 1529 NOKOMIS, FL 34274 (941)-480-1600	5/7/13	J ROSOWSKI	MD-555.1	A
VINYL FRENCH DOOR AND SLT/TR	Date	By	DWG	Rev.
INSTALLATION 1	Sheet	7 OF 12	NTS	FD-5555
Scale	Scale	Scale	Scale	Scale






INSTALLATION NOTES:


- 1) USE ONLY SUBSTRATE-APPROPRIATE ANCHORS LISTED ON TABLE 1, SHEET 1. FOLLOW EMBEDMENT AND EDGE DISTANCE LIMITS. ANY INSTALLATION OPTION SHOWN MAY BE USED ON ANY SIDE OF THE DOOR, SIDELITE OR TRANSOM.
- 2) WOOD BUCKS DEPICTED ON THIS SHEET AS "1X", ARE BUCKS WHOSE TOTAL THICKNESS IS LESS THAN 1-1/2". 1X WOOD BUCKS ARE OPTIONAL IF UNIT CAN BE INSTALLED DIRECTLY TO MASONRY. WOOD BUCKS DEPICTED AS "2X" ARE 1-1/2" THICK OR GREATER. INSTALLATION TO THE SUBSTRATE OF WOOD BUCKS TO BE ENGINEERED BY OTHERS OR AS APPROVED BY THE AUTHORITY HAVING JURISDICTION.
- 3) FOR ATTACHMENT TO METAL: THE STRUCTURAL MEMBER SHALL BE OF A SIZE TO PROVIDE FULL SUPPORT TO THE FRAME OF THE DOOR, SIDELITE OR TRANSOM.
- 4) IF APPLICABLE, LOWEST DESIGN PRESSURE FROM DOOR, SIDELITE, TRANSOM OR MULLION APPLIES TO THE WHOLE SYSTEM.

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0409.03
Expiration Date 01/23/2019
By Manuel Perez
Miami Dade Product Control

Rev A NO CHANGES THIS SHEET -
JR - 03/18/15
Rev B
Rev C

1070 TECHNOLOGY DRIVE N. VENICE, FL 34275 P.O. BOX 1529 NOKOMIS, FL 34274 (941) 480-1600	Date	5/7/13	By	J ROSOWSKI	Rev	A
VINYL FRENCH DOOR AND SLT/R	Sheet	8 OF 12	Scale	NTS	DWC	MD-555.1
INSTALLATION 2	Series	FD-5555	Desc.	Title	No.	A





INSTALLATION NOTES:


1) USE ONLY SUBSTRATE-APPROPRIATE ANCHORS LISTED ON TABLE 1, SHEET 1. FOLLOW EMBEDMENT AND EDGE DISTANCE LIMITS. ANY INSTALLATION OPTION SHOWN MAY BE USED ON ANY SIDE OF THE DOOR, SIDELITE OR TRANSOM.

2) WOOD BUCKS DEPICTED ON THIS SHEET AS "1X", ARE BUCKS WHOSE TOTAL THICKNESS IS LESS THAN 1-1/2". 1X WOOD BUCKS ARE OPTIONAL IF UNIT CAN BE INSTALLED DIRECTLY TO MASONRY. WOOD BUCKS DEPICTED AS "2X" ARE 1-1/2" THICK OR GREATER. INSTALLATION TO THE SUBSTRATE OF WOOD BUCKS TO BE ENGINEERED BY OTHERS OR AS APPROVED BY THE AUTHORITY HAVING JURISDICTION.


3) FOR ATTACHMENT TO METAL: THE STRUCTURAL MEMBER SHALL BE OF A SIZE TO PROVIDE FULL SUPPORT TO THE FRAME OF THE DOOR, SIDELITE OR TRANSOM.

4) IF APPLICABLE, LOWEST DESIGN PRESSURE FROM DOOR, SIDELITE, TRANSOM OR MULLION APPLIES TO THE WHOLE SYSTEM.


INSTALLATION OPTION 3 INSTALLATION ANCHORS THROUGH 1X BUCKSTRIP INTO MASONRY.



INSTALLATION OPTION 4 INSTALLATION ANCHORS THROUGH 1X BUCKSTRIP INTO 2X WOOD.



INSTALLATION OPTION 2 INSTALLATION ANCHORS DIRECTLY INTO MASONRY.





PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0409.03
Expiration Date 07/23/2019
By *Manuel Perez*
Miami Dade Product Control

Rev. A) NO CHANGES THIS SHEET -
JR - 03/18/15

1070 TECHNOLOGY DRIVE N. VENICE, FL 34275 P.O. BOX 1529 NOKOMIS, FL 34274 (941) 480-1600	Date	5/7/13	By	J ROSOWSKI	No.	9 OF 12	Sheet	NTS	Scale	FD-5555	Series	Rev.	A
												MD-555.1	

PG
CERT. OF AUTH. #29296





PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0409.03
Expiration Date 6/23/2019
By *Manuel Perez*
Miami Dade Product Control

Rev A
Rev B
Rev C
Rev D
Rev E
Rev F
Rev G
Rev H
Rev I
Rev J
Rev K
Rev L
Rev M
Rev N
Rev O
Rev P
Rev Q
Rev R
Rev S
Rev T
Rev U
Rev V
Rev W
Rev X
Rev Y
Rev Z
Rev AA
Rev AB
Rev AC
Rev AD
Rev AE
Rev AF
Rev AG
Rev AH
Rev AI
Rev AJ
Rev AK
Rev AL
Rev AM
Rev AN
Rev AO
Rev AP
Rev AQ
Rev AR
Rev AS
Rev AT
Rev AU
Rev AV
Rev AW
Rev AX
Rev AY
Rev AZ
Rev BA
Rev BB
Rev BC
Rev BD
Rev BE
Rev BF
Rev BG
Rev BH
Rev BI
Rev BJ
Rev BK
Rev BL
Rev BM
Rev BN
Rev BO
Rev BP
Rev BQ
Rev BR
Rev BS
Rev BT
Rev BU
Rev BV
Rev BW
Rev BX
Rev BY
Rev BZ
Rev CA
Rev CB
Rev CC
Rev CD
Rev CE
Rev CF
Rev CG
Rev CH
Rev CI
Rev CJ
Rev CK
Rev CL
Rev CM
Rev CN
Rev CO
Rev CP
Rev CQ
Rev CR
Rev CS
Rev CT
Rev CU
Rev CV
Rev CW
Rev CX
Rev CY
Rev CZ
Rev DA
Rev DB
Rev DC
Rev DD
Rev DE
Rev DF
Rev DG
Rev DH
Rev DI
Rev DJ
Rev DK
Rev DL
Rev DM
Rev DN
Rev DO
Rev DP
Rev DQ
Rev DR
Rev DS
Rev DT
Rev DU
Rev DV
Rev DW
Rev DX
Rev DY
Rev DZ
Rev EA
Rev EB
Rev EC
Rev ED
Rev EE
Rev EF
Rev EG
Rev EH
Rev EI
Rev EJ
Rev EK
Rev EL
Rev EM
Rev EN
Rev EO
Rev EP
Rev EQ
Rev ER
Rev ES
Rev ET
Rev EU
Rev EV
Rev EW
Rev EX
Rev EY
Rev EZ
Rev FA
Rev FB
Rev FC
Rev FD
Rev FE
Rev FF
Rev FG
Rev FH
Rev FI
Rev FJ
Rev FK
Rev FL
Rev FM
Rev FN
Rev FO
Rev FP
Rev FQ
Rev FR
Rev FS
Rev FT
Rev FU
Rev FV
Rev FW
Rev FX
Rev FY
Rev FZ
Rev GA
Rev GB
Rev GC
Rev GD
Rev GE
Rev GF
Rev GG
Rev GH
Rev GI
Rev GJ
Rev GK
Rev GL
Rev GM
Rev GN
Rev GO
Rev GP
Rev GQ
Rev GR
Rev GS
Rev GT
Rev GU
Rev GV
Rev GW
Rev GX
Rev GY
Rev GZ
Rev HA
Rev HB
Rev HC
Rev HD
Rev HE
Rev HF
Rev HG
Rev HH
Rev HI
Rev HJ
Rev HK
Rev HL
Rev HM
Rev HN
Rev HO
Rev HP
Rev HQ
Rev HR
Rev HS
Rev HT
Rev HU
Rev HV
Rev HW
Rev HX
Rev HY
Rev HZ
Rev IA
Rev IB
Rev IC
Rev ID
Rev IE
Rev IF
Rev IG
Rev IH
Rev II
Rev IJ
Rev IK
Rev IL
Rev IM
Rev IN
Rev IO
Rev IP
Rev IQ
Rev IR
Rev IS
Rev IT
Rev IU
Rev IV
Rev IW
Rev IX
Rev IY
Rev IZ
Rev JA
Rev JB
Rev JC
Rev JD
Rev JE
Rev JF
Rev JG
Rev JH
Rev JI
Rev JJ
Rev JK
Rev JL
Rev JM
Rev JN
Rev JO
Rev JP
Rev JQ
Rev JR
Rev JS
Rev JT
Rev JU
Rev JV
Rev JW
Rev JX
Rev JY
Rev JZ
Rev KA
Rev KB
Rev KC
Rev KD
Rev KE
Rev KF
Rev KG
Rev KH
Rev KI
Rev KJ
Rev KK
Rev KL
Rev KM
Rev KN
Rev KO
Rev KP
Rev KQ
Rev KR
Rev KS
Rev KT
Rev KU
Rev KV
Rev KW
Rev KX
Rev KY
Rev KZ
Rev LA
Rev LB
Rev LC
Rev LD
Rev LE
Rev LF
Rev LG
Rev LH
Rev LI
Rev LJ
Rev LK
Rev LL
Rev LM
Rev LN
Rev LO
Rev LP
Rev LQ
Rev LR
Rev LS
Rev LT
Rev LU
Rev LV
Rev LW
Rev LX
Rev LY
Rev LZ
Rev MA
Rev MB
Rev MC
Rev MD
Rev ME
Rev MF
Rev MG
Rev MH
Rev MI
Rev MJ
Rev MK
Rev ML
Rev MM
Rev MN
Rev MO
Rev MP
Rev MQ
Rev MR
Rev MS
Rev MT
Rev MU
Rev MV
Rev MW
Rev MX
Rev MY
Rev MZ
Rev NA
Rev NB
Rev NC
Rev ND
Rev NE
Rev NF
Rev NG
Rev NH
Rev NI
Rev NJ
Rev NK
Rev NL
Rev NM
Rev NN
Rev NO
Rev NP
Rev NQ
Rev NR
Rev NS
Rev NT
Rev NU
Rev NV
Rev NW
Rev NX
Rev NY
Rev NZ
Rev OA
Rev OB
Rev OC
Rev OD
Rev OE
Rev OF
Rev OG
Rev OH
Rev OI
Rev OJ
Rev OK
Rev OL
Rev OM
Rev ON
Rev OO
Rev OP
Rev OQ
Rev OR
Rev OS
Rev OT
Rev OU
Rev OV
Rev OW
Rev OX
Rev OY
Rev OZ
Rev PA
Rev PB
Rev PC
Rev PD
Rev PE
Rev PF
Rev PG
Rev PH
Rev PI
Rev PJ
Rev PK
Rev PL
Rev PM
Rev PN
Rev PO
Rev PP
Rev PQ
Rev PR
Rev PS
Rev PT
Rev PU
Rev PV
Rev PW
Rev PX
Rev PY
Rev PZ
Rev QA
Rev QB
Rev QC
Rev QD
Rev QE
Rev QF
Rev QG
Rev QH
Rev QI
Rev QJ
Rev QK
Rev QL
Rev QM
Rev QN
Rev QO
Rev QP
Rev QQ
Rev QR
Rev QS
Rev QT
Rev QU
Rev QV
Rev QW
Rev QX
Rev QY
Rev QZ
Rev RA
Rev RB
Rev RC
Rev RD
Rev RE
Rev RF
Rev RG
Rev RH
Rev RI
Rev RJ
Rev RK
Rev RL
Rev RM
Rev RN
Rev RO
Rev RP
Rev RQ
Rev RR
Rev RS
Rev RT
Rev RU
Rev RV
Rev RW
Rev RX
Rev RY
Rev RZ
Rev SA
Rev SB
Rev SC
Rev SD
Rev SE
Rev SF
Rev SG
Rev SH
Rev SI
Rev SJ
Rev SK
Rev SL
Rev SM
Rev SN
Rev SO
Rev SP
Rev SQ
Rev SR
Rev SS
Rev ST
Rev SU
Rev SV
Rev SW
Rev SX
Rev SY
Rev SZ
Rev TA
Rev TB
Rev TC
Rev TD
Rev TE
Rev TF
Rev TG
Rev TH
Rev TI
Rev TJ
Rev TK
Rev TL
Rev TM
Rev TN
Rev TO
Rev TP
Rev TQ
Rev TR
Rev TS
Rev TT
Rev TU
Rev TV
Rev TW
Rev TX
Rev TY
Rev TZ
Rev UA
Rev UB
Rev UC
Rev UD
Rev UE
Rev UF
Rev UG
Rev UH
Rev UI
Rev UJ
Rev UK
Rev UL
Rev UM
Rev UN
Rev UO
Rev UP
Rev UQ
Rev UR
Rev US
Rev UT
Rev UY
Rev UZ
Rev VA
Rev VB
Rev VC
Rev VD
Rev VE
Rev VF
Rev VG
Rev VH
Rev VI
Rev VJ
Rev VK
Rev VL
Rev VM
Rev VN
Rev VO
Rev VP
Rev VQ
Rev VR
Rev VS
Rev VT
Rev VY
Rev VZ
Rev WA
Rev WB
Rev WC
Rev WD
Rev WE
Rev WF
Rev WG
Rev WH
Rev WI
Rev WJ
Rev WK
Rev WL
Rev WM
Rev WN
Rev WO
Rev WP
Rev WQ
Rev WR
Rev WS
Rev WT
Rev WY
Rev WZ
Rev XA
Rev XB
Rev XC
Rev XD
Rev XE
Rev XF
Rev XG
Rev XH
Rev XI
Rev XJ
Rev XK
Rev XL
Rev XM
Rev XN
Rev XO
Rev XP
Rev XQ
Rev XR
Rev XS
Rev XT
Rev XZ
Rev YA
Rev YB
Rev YC
Rev YD
Rev YE
Rev YF
Rev YG
Rev YH
Rev YI
Rev YJ
Rev YK
Rev YL
Rev YM
Rev YN
Rev YO
Rev YP
Rev YQ
Rev YR
Rev YS
Rev YT
Rev YZ
Rev ZA
Rev ZB
Rev ZC
Rev ZD
Rev ZE
Rev ZF
Rev ZG
Rev ZH
Rev ZI
Rev ZJ
Rev ZK
Rev ZL
Rev ZM
Rev ZN
Rev ZO
Rev ZP
Rev ZQ
Rev ZR
Rev ZS
Rev ZT
Rev ZY
Rev ZZ

1070 TECHNOLOGY DRIVE N. VENICE, FL 34275 P.O. BOX 1529 NOKOMIS, FL 34274 (941) 480-1600	VINYL FRENCH DOOR AND SLT/RR	J ROSOWSKI	5/7/13	A
FD-5555	NTS	10 OF 12	MD-555.1	A





TABLE 11:

#	PGT Part #	Description	Material
1	20000	Door & Sidelite/Transom Main Frame	Cellular PVC
2	20001	Door Frame Sill	Rigid PVC
3	20002	Panel Stile & Rail	Cellular PVC
4	20003	Sidelite Adapter	Rigid PVC
5	20013	Hinge Stile Reinforcement	Alum., 6063-T6
6	20014	Panel Rail Reinforcement	Alum., 6063-T6
7	20015	Panel Stile Reinforcement	Alum., 6063-T6
8	20016	Active Astragal	Rigid PVC
9	20017	Inactive Astragal	Rigid PVC
10	20022	1" French Door Mullion	Alum., 6063-T6
13	20004	Inactive Astragal Cover	Rigid PVC
14	20005	1-1/16" Bevel Bead	Rigid PVC
15	20006	1-1/16" Ogee Bead	Rigid PVC
16	20007	Screw Cover	Rigid PVC
17	20008	Add-on Fin/Flange	Rigid PVC
18	20009	1" Mullion Cap	Rigid PVC
19	20011	Active Astragal Cover	Rigid PVC
20	20012	Single Door Astragal Cover	Rigid PVC
22	20018	Sill Screw Cover	Rigid PVC
23	19031	Anchor Plate	Alum., 6063-T6
24	20020	Threshold Cover	Alum., 6063-T6
25	20021	Drip Cap	Rigid PVC
26	20023	Hinge Trim Cover	Rigid PVC
28		Fin Weatherstrip	
29	1671/3	Frame Weatherstrip	
31	714FPT410XW	Frame-to-Wide Slab Screw: #14 X 1-1/2" Ph. FH, 16.625" O.C.	Stainless Steel
32	7S101X	Frame-to-Nar. Slab Screw: #10 X 1" Ph. FH, 28" O.C.	Stainless Steel
33	78X1FPT410	Reinforcement Screw: #8 X 1" Ph. FH, 18" O.C.	Stainless Steel
34	710X2FPAX	Frame Assembly Screw: #10 X 2" Ph. FH	Stainless Steel
35	714FPT410XW	W-W Slab Assembly Screw: #14 X 1-1/2" Ph. FH	Stainless Steel
37	71420X2.25	N-W Slab Assembly Screw: #14 X 2-1/4" Ph. FH	Stainless Steel
38		Cardinal XL Edge Spacer	
39		Quanex DuraSeal Spacer, Composite Sealant/Dessicant	
40	62689	Quanex SuperSpacer, Foam EPDM w/ Dessicant	
41	720026	Setting Block, (Duro.=85 +/- 5)	EPDM
42		Backbedding: Dow-995 or GE-7700	Silicone
43		Argon Gas	
44	6HL5140	Hot Melt Butyl	
47 - 73 see Hardware BOM, Table 12, Sheet 12			
90	20033	Inactive Astragal Cap	Acetal
91	20035	Active Astragal Cap	Acetal

ALL RIGID PVC AND RIGID CELLULAR PVC BY VISION EXTRUSIONS, LTD.
ANCHOR O.C. DIMENSIONS SHOWN AS MAXIMUM.

DAYLITE OPENING (DLO) SIZES

WHEN USING PART # 3: (WIDE RAILS OR STILES)
X DOOR FRAME HEIGHT - 12.1 = DLO HEIGHT
X DOOR FRAME WIDTH - 12.3 = DLO WIDTH
(XX DOOR FRAME HEIGHT) - 12.1 = DLO HEIGHT
(XX DOOR FRAME WIDTH / 2) - 11.5 = DLO WIDTH
SLT/TR FRAME HEIGHT - 12.1 = DLO HEIGHT
SLT/TR FRAME WIDTH - 12.1 = DLO WIDTH
WHEN USING PART # 4: (NARROW RAILS OR STILES)
SLT/TR FRAME HEIGHT - 4.9 = DLO HEIGHT
SLT/TR FRAME WIDTH - 4.9 = DLO WIDTH



PRODUCT REVISED
as complying with the Florida
Building Code 15-0409.03
Acceptance No. 01/23/2019
Expiration Date
By *Manuel*
Miami Dade Product Control

Rev A
Rev B
Rev C
A) ADDED #38 - JR - 03/18/15

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
(941)-480-1600

5/7/13

DATE

J ROSOWSKI

DRAWN BY

MD-555.1

REV

A

11 OF 12

SHEET

FD-5555

SCALE

NTS

CORNER DETAILS AND BOM

VINYL FRENCH DOOR AND SLT/TR

CERT. OF AUTH. #29296

RG

ANTHONY LYNN MILLER
LICENSE
No. 58705
6/16/15
STATE OF
FLORIDA
PROFESSIONAL ENGINEER

A. LYNN MILLER, P.E.
P.E.# 58705

HARDWARE DETAILS & LOCATIONS





TABLE 12:

#	PGT Part #	Description	Material
47	666032701	P3000 3-PT Rhino Lock (6'8\"), Amesbury Inc.	Stainless Steel
48	666032702	P3000 3-PT Rhino Lock (over 6'8\"), Amesbury Inc.	Stainless Steel
49	71032X1FPFX	Rhino Lock Screw: 10-32 X 1\" Phil. FH	Stainless Steel
52	20027	Adjustable Strike Plate Assembly, Amesbury Inc.	Stainless Steel
53	20028	Center Strike Plate Assembly, Amesbury Inc.	Stainless Steel
54	7S101X	Strike Plate Screw, (X): #10 X 1\" Phil. FH	410 S.S.
55	78X12PFHUX	Strike Plate Screw, (XX): #8 X 1/2\" Phil. FH	410 S.S.
60	7SB1202	Flush Bolt (XX)	
61	7803725	Flush Bolt Rod (XX)	
62	420034	Flush Bolt Guide (XX)	
63	7832X12FPXP	Flush Bolt Guide Screw: 8-32 X 1/2\" Phil. FH	
64	48033N	Guide Pin (XX)	
65	78036	Flush Bolt Strike Plate (XX), Amesbury Inc.	Stainless Steel
66	7832X12FPXP	Flush Bolt Strike Plate Screw, (XX): #8 X 3/4\" Phil. FH	410 S.S.
67	varies	Handle/Lever	
68	varies	Dummy Handle/Lever	
70	20025	Butt Hinge, Amesbury Inc.	Stainless Steel
71	71032X1FPFX	Hinge, Slab Screw: #10-32 X 1\" Phil FH	Stainless Steel
72	7S101X	Hinge, Frame Screw: #10 X 1\" Phil. FH	Stainless Steel

HINGE DETAIL:



SEE DETAIL,
TOP LOCK
SIMILAR

9/16\"
BEYOND
PANEL

FLUSH BOLT DETAIL:

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0409.03
Expiration Date 01/23/2019
By *Manuel Perez*
Miami Dade Product Control

Rev A	A) NO CHANGES THIS SHEET - JR - 03/18/15
Rev B	
Rev C	

1070 TECHNOLOGY DRIVE N. VENICE, FL 34275 P.O. BOX 1529 NOKOMIS, FL 34274 (941) 480-1600	Date By J ROSOWSKI Drawn	No. DWG 12 OF 12	Scale NTS	Sheet FD-5555	Title DESIGN PRESSURE TABLES 3	Series VINYL FRENCH DOOR AND SLT/FR	Rev. A
							MD-555.1

