



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION

NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY
PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208
T (786) 315-2590 F (786) 315-2599

www.miamidade.gov/economy

PGT Industries
1070 Technology Drive
North Venice, FL 34275

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.-

DESCRIPTION: Series "CA-740" Outswing Aluminum Casement Window - L.M.I.

APPROVAL DOCUMENT: Drawing No. MD-CA740-LM, titled "Casement Window Details - LM & SM", sheets 1 through 10 of 10, dated 08/08/12, with revision A dated 05/15/15, prepared by manufacturer, signed and sealed by Anthony Lynn Miller, P.E., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, model/series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises NOA# 12-1218.09 and consists of this page 1 and evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by **Manuel Perez, P.E.**



MP
7/15/15

NOA No. 15-0519.13
Expiration Date: April 11, 2018
Approval Date: July 16 2015
Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.
(Submitted under previous NOA No. 12-1218.09)
2. Drawing No. **MD-CA740-LM**, titled "Casement Window Details – LM & SM", sheets 1 through 10 of 10, dated 08/08/12, with revision A dated 05/15/15, signed and sealed by Anthony Lynn Miller, P.E.

B. TESTS

1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
4) Large Missile Impact Test per FBC, TAS 201-94
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
6) Forced Entry Test, per FBC 2411.3.2.1, and TAS 202-94
along with marked-up drawings and installation diagram of a series CA740 outswing aluminum casement window, prepared by Fenestration Testing Laboratory, Inc. Test Report No. **FTL-7065**, dated 10/05/12, signed and sealed by Marlin D. Brinson, P.E.
(Submitted under previous NOA No. 12-1218.09)

C. CALCULATIONS

1. Anchor verification calculations and structural analysis, complying with **FBC-5th Edition (2014)**, dated 05/16/15, prepared by manufacturer, signed and sealed by Anthony Lynn Miller, P.E.
2. Glazing complies with **ASTM E1300-04**

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER).

E. MATERIAL CERTIFICATIONS

1. Notice of Acceptance No. **14-0916.10** issued to **Kuraray America, Inc.** for their "**Kuraray Butacite® PVB Glass Interlayer**" dated 04/25/15, expiring on 12/11/16.
2. Notice of Acceptance No. **14-0916.11** issued to **Kuraray America, Inc.** for their "**Kuraray SentryGlas® (Clear and White) Glass Interlayers**" dated 06/25/15, expiring on 07/04/18.


Manuel Perez, P.E.
Product Control Examiner
NOA No. 15-0519.13

Expiration Date: April 11, 2018
Approval Date: July 16 2015

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

F. STATEMENTS

1. Statement letter of conformance, complying with **FBC-5th Edition (2014)**, dated May 16, 2015, issued by manufacturer, signed and sealed by Anthony Lynn Miller, P.E.
2. Statement letter of no financial interest, dated May 16, 2015, issued by manufacturer, signed and sealed by Anthony Lynn Miller, P.E.

G. OTHERS

1. Notice of Acceptance No. **12-1218.09**, issued to PGT Industries for their Series "CA-740" Outswing Aluminum Casement Window - L.M.I." approved on 04/11/13 and expiring on 04/11/18.



Manuel Perez, P.E.
Product Control Examiner
NOA No. 15-0519.13

Expiration Date: April 11, 2018
Approval Date: July 16 2015

GENERAL NOTES: SERIES 740 IMPACT-RESISTANT CASEMENT WINDOW

1) THIS PRODUCT HAS BEEN DESIGNED & TESTED TO COMPLY WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE, INCLUDING THE HIGH VELOCITY HURRICANE ZONE (HVHZ).

2) SHUTTERS ARE NOT REQUIRED WHEN USED IN WIND-BORNE DEBRIS REGIONS. FOR INSULATED GLASS INSTALLATIONS ABOVE 30" IN THE HVHZ, THE OUTBOARD LITE (CAP) MUST TEMPERED.

3) FOR MASONRY APPLICATIONS IN MIAMI-DADE COUNTY, USE ONLY MIAMI-DADE COUNTY APPROVED MASONRY ANCHORS. MATERIALS USED FOR ANCHOR EVALUATIONS WERE SOUTHERN PINE, ASTM C90 CONCRETE MASONRY UNITS AND CONCRETE WITH MIN. KSI PER ANCHOR TYPE, SEE TABLE 3, SHEET 4.

4) ALL WOOD BUCKS LESS THAN 1-1/2" THICK ARE TO BE CONSIDERED 1X INSTALLATIONS. 1X WOOD BUCKS ARE OPTIONAL IF UNIT IS INSTALLED DIRECTLY TO SUBSTRATE. WOOD BUCKS DEPICTED AS 2X ARE 1-1/2" THICK OR GREATER. 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED TO PROPERLY TRANSFER LOADS TO THE STRUCTURE. WOOD BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD.

5) ANCHOR EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO. USE ANCHORS OF SUFFICIENT EMBEDMENT AS SPECIFIED ON TABLE 3, SHEET 4. NARROW JOINT SEALANT IS USED ON ALL FOUR CORNERS OF THE FRAME. INSTALLATION ANCHORS SHOULD BE SEALED. OVERALL SEALING/FLASHING STRATEGY FOR WATER RESISTANCE OF INSTALLATION SHALL BE DONE BY OTHERS AND IS BEYOND THE SCOPE OF THESE INSTRUCTIONS.


6) SHIMS ARE REQUIRED AT EACH ANCHOR LOCATION WHERE THE PRODUCT IS NOT FLUSH TO THE SUBSTRATE. USE SHIMS CAPABLE OF TRANSFERRING APPLIED LOADS. WOOD BUCKS, BY OTHERS, MUST BE SUFFICIENTLY ANCHORED TO RESIST LOADS IMPOSED ON THEM BY THE WINDOW.

7) DESIGN PRESSURES:
A. NEGATIVE DESIGN LOADS BASED ON STRUCTURAL/CYCLE TEST PRESSURE, FRAME ANALYSIS AND GLASS PER ASTM E1300.
B. POSITIVE DESIGN LOADS BASED ON WATER TEST PRESSURE, STRUCTURAL/ CYCLE TEST PRESSURE, FRAME ANALYSIS AND GLASS PER ASTM E1300.


8) THE ANCHORAGE METHODS SHOWN HAVE BEEN DESIGNED TO RESIST THE WINDLOADS CORRESPONDING TO THE REQUIRED DESIGN PRESSURE. THE 33-1/3% STRESS INCREASE HAS NOT BEEN USED IN THE DESIGN OF THIS PRODUCT. THE 1.6 LOAD DURATION FACTOR WAS USED FOR THE EVALUATION OF ANCHORS INTO WOOD. ANCHORS THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF THE FLORIDA BUILDING CODE FOR CORROSION RESISTANCE.

9) REFERENCES: TEST REPORTS FTL-7065, 3579, 3580, 3724; ELCO ULTRACON NOA; ELCO CRETEFLEX NOA; ANSI/AF&PA NDS FOR WOOD CONSTRUCTION AND ADM ALUMINUM DESIGN MANUAL.


DESIGN PRESSURE RATING	IMPACT RATING
VARIABLES, SEE SHEETS 5-9	RATED FOR LARGE & SMALL MISSILE IMPACT RESISTANCE




TYP. ELEVATION OF
CASEMENT WINDOW




GLASS TYPE 1




GLASS TYPES 2 & 3



GLASS TYPES 4 & 5



GLASS TYPES 6 & 7




GLASS TYPES 8 & 9

TABLE 1:

Glass Types	Sheet #
1 5/16" Lami (1/8 An - .090" PVB - 1/8 An)	5
2 7/16" Lami (3/16 An - .090" SG - 3/16 An)	6
3 7/16" Lami (3/16 HS - .090" SG - 3/16 HS)	7
4 7/8" Lami. IG (1/8" An - 7/16" Air - 1/8" An - .090" PVB - 1/8" An)	5
5 7/8" Lami. IG (1/8" T - 7/16" Air - 1/8" An - .090" PVB - 1/8" An)	8
6 7/8" Lami. IG (3/16" An - 1/4" Air - 3/16" An - .090" SG - 3/16" An)	9
7 7/8" Lami. IG (3/16" An - 1/4" Air - 3/16" HS - .090" SG - 3/16" HS)	7
8 7/8" Lami. IG (3/16" T - 1/4" Air - 3/16" An - .090" SG - 3/16" An)	9
9 7/8" Lami. IG (3/16" T - 1/4" Air - 3/16" HS - .090" SG - 3/16" HS)	7

"PVB"= BUTACITE® PVB BY KURARAY AMERICA, INC.
"SG"= SENTRYGLAS® BY KURARAY AMERICA, INC.

GENERAL NOTES.....	1
ELEVATION.....	1
GLAZING DETAILS.....	1
INSTALLATION.....	2
ASSEMBLY TUBE DETAILS.....	3
ANCHOR SPECIFICATIONS.....	4
ANCHOR QUANTITIES.....	4
DESIGN PRESSURES.....	5-9
ASSEMBLY DETAILS/BOM.....	10



1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274

CERT. OF AUTH. #29296


Revised By:	Date:	Revision B:
LM	5/15/15	
Revised By:	Date:	Revision A:
		5TH EDITION (2014) FBC UPDATE
Description:	GLAZING DETAILS	
Title:	CASEMENT WINDOW DETAILS - LM & SM	
Series/Model:	CA-740	Scale:
Sheet:	1 OF 10	Sheet:
Drawing No.	MD-CA740-LM	Rev:
		A

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0519.13
Expiration Date April 11, 2018
By: *Manuel Lopez*
Miami Dade Product Control

Drawn By:
J ROSOWSKI

Date:
08/08/12


INSTALLATION OPTION 1 INSTALLATION ANCHORS INTO 2X WOOD.



INSTALLATION OPTION 3 INSTALLATION ANCHORS THROUGH 1X BUCKSTRIP INTO MASONRY.



VERTICAL SECTION B-B

INSTALLATION OPTION 2 INSTALLATION ANCHORS DIRECTLY INTO MASONRY.




- NOTES:**
- 1) USE ONLY SUBSTRATE-APPROPRIATE ANCHORS LISTED ON TABLE 3, SHEET 4. FOLLOW EMBEDMENT AND EDGE DISTANCE LIMITS. ANY INSTALLATION OPTION SHOWN MAY BE USED ON ANY SIDE OF THE WINDOW.
 - 2) ALL WOOD BUCKS LESS THAN 1-1/2" THICK ARE TO BE CONSIDERED 1X INSTALLATIONS. 1X WOOD BUCKS ARE OPTIONAL. UNIT MAY BE INSTALLED DIRECTLY TO SUBSTRATE. WOOD BUCKS DEPICTED AS 2X ARE 1-1/2" THICK OR GREATER. 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED TO PROPERLY TRANSFER LOADS TO THE STRUCTURE. WOOD BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD. MAXIMUM SHIM THICKNESS TO BE 1/4".

SEE DETAIL
A1, BELOW




DETAIL
A1

HORIZONTAL SECTION A-A




10" MAX.

10" MAX.



DETAIL
A2

INSTALLATION OPTION 4 INSTALLATION ANCHORS DIRECTLY INTO METAL.




- EGRESS FORMULAS:**
- WIDTH, WASH HINGE: WINDOW WIDTH - 13-1/2"
WIDTH, EGRESS HINGE: WINDOW WIDTH - 7-1/2"
HEIGHT: WINDOW HEIGHT - 6"
- VISIBLE LIGHT FORMULAS:**
- WIDTH: WINDOW WIDTH - 7"
HEIGHT: WINDOW HEIGHT - 7"

- NOTES:**
- 1) WHEN INSTALLING COMBINATION UNITS, ADDITIONAL INSTALLATION ANCHORS MAY NEED TO BE INSTALLED THROUGH THE WINDOW FRAMES AT 10" MAX. FROM EACH SIDE OF THE FRAME ASSEMBLY TUBE CENTERLINE. SEE TABLE BELOW:

Additional Anchors Required on each Side of the Frame Assembly Tube (FAT)			
Vertical FAT	Window Width	Anchor Type	
		A	B, C & D
	17" - 22.9"	0	0
Horizontal FAT	Window Height	Anchor Type	
		A	B, C & D
	17" - 22.9"	0	0

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0519.13
Expiration Date April 11, 2018
By *Manuel Perez*
Miami/Dade Product Control



1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274

CERT. OF AUTH. #29296

Revised By:	Date:	Revision B:
LM	5/15/15	NO CHANGE THIS SHEET

Description:
CROSS SECTIONS & INSTALLATION


Title:
CASEMENT WINDOW DETAILS - LM & SM

Series/Model:	Scale:	Sheet:	Drawing No.	Rev:
CA-740	NTS	2 OF 10	MD-CA740-LM	A

Drawn By:
J ROSOWSKI

Date:
08/08/12

A diagram of a window with a double frame. To the left of the window, a vertical double-headed arrow is labeled "WINDOW HEIGHT". Below the window, a horizontal double-headed arrow is labeled "WINDOW WIDTH". Inside the window frame, there are dashed diagonal lines forming an 'X' shape, and a thick white arrow pointing towards the center of the window.



6) INSTALL AS PER THE INSTRUCTIONS ON SHEET 2.

FIGURE 1:


10", SEE NOTE 7, THIS SHEET

740
SERIES
CASEMENT
WINDOW

FRAME
ASSEMBLY
TUBE

740
SERIES
CASEMENT
WINDOW

10", SEE NOTE 7, THIS SHEET



5) INSTALL AS PER THE INSTRUCTIONS ON SHEETS 2-3. NOTE THAT ADDITIONAL ANCHORS THROUGH THE WINDOW FRAME INTO THE SUBSTRATE MAY BE REQUIRED (SEE SHEET 2), AND THAT MIN. #12 X 1" ANCHORS ARE TO BE USED THROUGH THE FRAME INTO THE FRAME ASSEMBLY TUBE (SEE DETAILS ON THIS SHEET).

FIGURE 2:

The diagram illustrates a vertical stack of three window units. The top unit is a 740 Series Awning Window, the middle is a 740 Series Casement Window, and the bottom is a 740 Series Fixed Window. Each unit is shown with its internal frame assembly tube. Callouts D and E point to the frame assembly tubes of the top and bottom units, respectively. Arrows indicate the opening and closing mechanism for the awning and casement windows. A note at the bottom states: *SEE PRODUCT'S NOA FOR INSTALLATION SPECS.

740 SERIES
AWNING
WINDOW*



FRAME
ASSEMBLY
TUBE

740 SERIES
CASEMENT
WINDOW

FRAME
ASSEMBLY
TUBE

740 SERIES
FIXED WINDOW*

*SEE PRODUCT'S NOA FOR
INSTALLATION SPECS



VERTICAL SECTION E-E

7) FOR ALL COMBINATION UNITS, ADDITIONAL INSTALLATION ANCHORS MAY NEED TO BE INSTALLED THROUGH THE WINDOW FRAMES AT 10" MAX. FROM EACH SIDE OF THE FRAME ASSEMBLY TUBE CENTERLINE. SEE TABLE BELOW:

Additional Anchors Required on each Side of the Frame Assembly Tube (FAT)			
Vertical FAT	Window Width	Anchor Type	
		A	B, C & D
	17" - 22.9"	0	0
	23" - 25.9"	0	1
	26"+	1	1
Horizontal FAT	Window Height	Anchor Type	
		A	B, C & D
	17" - 22.9"	0	0
	23" - 25.9"	0	1
	26"+	1	1

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 15-0519.13
Expiration Date Aug 11, 2018
By Mmanuel
Miami Dade Product Control

070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274

CERT. OF AUTH. #29296




TABLE 2:

Window Anchors Required																								
			Window Width (in)																					
			under 23"			25-15/16"			27-3/4"			30"			33-1/2"			35"			37"			
			Anchor Group			Anchor Group			Anchor Group			Anchor Group			Anchor Group			Anchor Group			Anchor Group			
			A	B	C & D	A	B	C & D	A	B	C & D	A	B	C & D	A	B	C & D	A	B	C & D	A	B	C & D	
Window Height (in)	under 23"	Jamb	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
		Head/Sill	2	2	2	2	2	2	2	2	2	2	2	3	2	2	3	2	3	3	3	3	3	3
	25-15/16"	Jamb	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
		Head/Sill	2	2	2	2	2	2	2	2	2	2	2	3	2	2	3	2	3	3	3	3	3	3
	38-3/8"	Jamb	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4
		Head/Sill	2	2	2	2	2	2	2	2	2	2	2	3	2	3	3	2	3	3	3	3	4	3
	48"	Jamb	4	4	4	4	6	4	4	6	4	4	6	4	4	6	4	4	6	4	6	6	4	4
		Head/Sill	2	2	2	2	2	2	2	2	2	2	3	2	3	3	2	3	3	3	3	4	3	3
	50-5/8"	Jamb	4	6	4	4	6	4	4	6	4	4	6	4	6	6	4	6	6	4	6	6	4	4
		Head/Sill	2	2	2	2	2	2	2	2	2	2	3	2	3	3	2	3	3	3	3	4	3	3
	60"	Jamb	6	6	4	6	6	4	6	8	4	6	8	4	6	8	4	6	8	4	6	8	4	4
		Head/Sill	2	2	2	2	2	2	2	2	2	2	3	2	3	3	2	3	3	3	3	4	3	3
	63"	Jamb	6	6	6	6	8	6	6	8	6	6	8	6	6	8	6	6	8	6	6	8	6	6
		Head/Sill	2	2	2	2	2	2	2	2	2	2	3	2	3	3	2	3	3	3	3	4	3	3
	72"	Jamb	6	8	6	6	8	6	8	8	6	8	10	6	8	10	6	8	10	6	8	10	6	6
		Head/Sill	2	2	2	2	2	2	2	2	2	2	3	2	2	3	2	3	3	3	3	3	3	3
76"	Jamb	6	8	6	8	8	6	8	10	6	8	10	6	8	10	6	8	10	6	8	10	6	6	
	Head/Sill	2	2	2	2	2	2	2	2	2	2	3	2	2	3	2	3	3	3	3	3	3	3	
84"	Jamb	8	8	6	8	10	6	8	10	6	8	10	6	8	10	6								
	Head/Sill	2	2	2	2	2	2	2	2	2	2	3	2	2	3	2								

TABLE 3:

Group	Anchor	Substrate	Min. Edge Distance	Min. O.C. Distance	Min. Embedment	Anchor Plate Required?
A	1/4" steel Ultracon	Hollow Block	1"	6"	1-1/4"	No
		S. Pine	5/8"	1"	1-3/8"	No
	#14, steel SMS (G5) or #14, 410 SS SMS	6063-T5 Alum.	3/8"	5/8"	.050"	No
		A36 Steel	3/8"	5/8"	.050"	No
B		A653 Stud, Gr. 33	3/8"	5/8"	.035", 20 Ga.	No
		S. Pine	5/8"	1"	1-3/8"	No
	#12, steel SMS (G5) or #12, 410 SS SMS	6063-T5 Alum.	3/8"	5/8"	.050"	No
		A36 Steel	3/8"	5/8"	.050"	No
C		A653 Stud, Gr. 33	3/8"	5/8"	.035", 20 Ga.	No
	1/4" steel Ultracon	2.85k Concrete	2-1/2"	4"	1-3/8"	No
		2.85k Concrete	1"	4"	1-3/4"	No
		Hollow Block	2-1/2"	5"	1-1/4"	No
D		S. Pine	5/8"	1"	1-3/8"	Yes
	#12, steel SMS (G5) or #12, 410 SS SMS	6063-T5 Alum.	3/8"	5/8"	.0713"	Yes
		A36 Steel	3/8"	5/8"	.050"	Yes
		A653 Stud, Gr. 33	3/8"	5/8"	.045", 18 Ga.	Yes
D		S. Pine	5/8"	1"	1-3/8"	Yes
	#14, steel SMS (G5) or #14, 410 SS SMS	6063-T5 Alum.	3/8"	5/8"	.0713"	Yes
		A36 Steel	3/8"	5/8"	.050"	Yes
		A653 Stud, Gr. 33	3/8"	5/8"	.045", 18 Ga.	Yes
	1/4" steel Ultracon	2.85k Concrete	1"	4"	1-3/4"	Yes
		2.85k Concrete	2-1/2"	4"	1-3/8"	Yes
		Hollow Block	2-1/2"	5"	1-1/4"	Yes
		Filled Block	2-1/2"	4"	1-3/4"	Yes
	1/4" 410 SS CreteFlex	3.35k Concrete	1"	5"	1-3/4"	No
		Hollow Block	2-1/2"	5"	1-1/4"	No
	5/16" steel Ultracon	3.5k Concrete	1-1/4"	5"	1-3/4"	No
		Hollow Block	3-1/8"	5"	1-1/4"	No
		Filled Block	2-1/2"	5"	1-3/4"	No

NOTES:

- 1) ANCHOR MUST EXTEND A MINIMUM OF 3 THREADS BEYOND ANY METAL SUBSTRATE.
2) ANCHORS MAY BE HEXHEAD, PANHEAD OR FLATHEAD.

TABLE 4:


		Jamb Snubber Locations	
		Glass Type:	
		PVB (Types 1, 4 & 5)	SG (Types 2, 3 & 6-9)
Window Height	63" and less	None Required	12" max. from each end & 30" max O.C.
	over 63"	12" max. from each end & 30" max O.C.	12" max. from each end & 30" max O.C.

"PVB"= BUTACITE® PVB BY KURARAY AMERICA, INC.
"SG"= SENTRYGLAS® BY KURARAY AMERICA, INC.

1) USE THIS TABLE FOR ALL WINDOWS PER THE ELEVATIONS ON SHEET 1. DIMENSIONS SHOWN ARE WINDOW TIP-TO-TIP.

2) FOR SIZES NOT SHOWN, ROUND UP TO THE NEXT AVAILABLE WIDTH OR HEIGHT DIMENSION SHOWN ON THE TABLE.

SAMPLE CONFIGURATIONS:



EXAMPLE 1: FOR WINDOW COMBINATION SHOWN BELOW; 7/16" ANNEALED SG LAMI. GLASS, 1/4" MASONRY ANCHORS INTO CONCRETE, +70/- 80 PSF DP REQUIRED, NO ANCHOR PLATE

CASEMENT ANCHORS:

A) FROM TABLE 9, ANCHORS C & D ALLOW A DP OF +70/-90.

B) FOR THE JAMB, FROM TABLE 3, ANCHOR TYPE C HAS THE ANCHOR AND SUBSTRATE DESIRED AND DOES NOT REQUIRE THE ANCHOR PLATE.

C) FROM TABLE 2, 6 ANCHORS ARE REQUIRED IN EACH JAMB.

D) SIMILARLY, 2 ANCHORS ARE REQUIRED IN THE HEAD & SILL.

E) DISTRIBUTE ANCHORS FOLLOWING GUIDELINES FROM ELEVATION ON SHEET 1.

F) PER RULES ON SHEETS 2 & 3, INSTALL 1 ADDITIONAL ANCHOR ON THE FRAME ASSEMBLY TUBE SIDE OF THE AWNING (HEAD & SILL).

FIXED CASEMENT ANCHORS (SEE SEPERATE NOA):

A) FROM TABLE 9, ANCHORS C & D ALLOW A DP OF +70/-83.1.


B) FOR THE JAMB, FROM TABLE 3, ANCHOR TYPE C HAS THE ANCHOR AND SUBSTRATE DESIRED AND DOES NOT REQUIRE THE ANCHOR PLATE.

C) FROM TABLE 2B, 5 ANCHORS ARE REQUIRED IN EACH JAMB.

D) SIMILARLY, 3 ANCHORS ARE REQUIRED IN THE HEAD & SILL.

E) DISTRIBUTE ANCHORS FOLLOWING GUIDELINES FROM ELEVATION ON SHEET 1.

F) PER RULES ON SHEET 2, INSTALL 1 ADDITIONAL ANCHOR ON THE FRAME ASSEMBLY TUBE SIDE OF THE FIXED CASEMENT (HEAD & SILL).



PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0519.13
Expiration Date April 11, 2018
By *Manuel J. Miller*
Miami Dade Product Control

Revision A: CHANGE ALUM. THICKNESS

Date: 5/15/15

Revised By: L MILLER

Drawn By: J ROSOWSKI

Date: 08/08/12

Description: ANCHOR TYPE AND QUANTITY

Title: CASEMENT WINDOW DETAILS - LM & SM

Scale: NTS

Sheet: 4 OF 10

Drawing No. MD-CA740-LM

Rev. A


CA-740

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
CERT. OF AUTH. #29296

ANTHONY LYNN MILLER
LICENSE
No. 58705
STATE OF FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
P.E. #58705

TABLE 5:

	Design Pressure (psf) for Single Windows, All Anchor Groups						
	Window Width						
	under 23"	25-15/16"	27-3/4"	30"	33-1/2"	35"	37"
Window Height	under 23"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	38-3/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	48"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-91
	50-5/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-89.2
	60"	+70/-90	+70/-90	+70/-90	+70/-88.5	+70/-80.6	+70/-77.7
	63"	+70/-90	+70/-90	+70/-90	+70/-84.3	+70/-76.5	+70/-73.7
	72"	+70/-90	+70/-87.2	+70/-77.7	+60/-71.5	+60/-62.4	+60/-60.9
	76"	+70/-90	+70/-84.6	+70/-75.7	+/-67.3	+/-58.9	+/-57.2
	84"	+70/-90	+70/-80.4	+70/-71.3	+60/-62.1	+/-54.2	



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES.

FOR GLASS TYPES:

- 1) 5/16" LAMI (1/8 AN - .090" PVB - 1/8 AN)
- 4) 7/8" LAMI. IG: (1/8" AN - 7/16" AIR - 1/8" AN - .090" PVB - 1/8" AN)

*PVB** BUTACITE®PVB BY KURARAY AMERICA, INC.


PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0519.13
Expiration Date April 11, 2018
By *Manuel Perez*
Miami Dade Product Control

TABLE 6:


	Design Pressure (psf) for Windows Attached to a Vertical Frame Assembly Tube																		
	Window Width																		
	under 23"				25-15/16"			27-3/4"		30"		33-1/2"			35"		37"		
	Anchor Group				Anchor Group			Anchor Group		Anchor Group		Anchor Group			Anchor Group		Anchor Group		
Window Height		A	B	C	D	A	B	C & D	B	A, C & D	B	A, C & D	A	B	C & D	B	A, C & D	B	A, C & D
	under 23"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	38-3/8"	+70/-90	+70/-71.6	+70/-90	+70/-90	+70/-81	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	48"	+70/-73.1	+/-57.3	+70/-90	+70/-90	+/-64.8	+70/-90	+70/-90	+70/-90	+70/-90	+70/-87.8	+70/-90	+70/-90	+70/-78.6	+70/-90	+70/-90	+70/-90	+70/-88.9	+70/-90
	50-5/8"	+/-69.3	+/-54.3	+70/-90	+70/-90	+/-61.4	+70/-90	+70/-90	+70/-90	+70/-90	+70/-83.2	+70/-90	+70/-90	+70/-74.6	+70/-90	+70/-89.2	+70/-90	+70/-84.3	+70/-89.2
	60"	+/-58.5	+/-45.8	+70/-84.7	+70/-90	+/-51.8	+70/-81.2	+70/-90	+70/-75.9	+70/-90	+70/-70.2	+70/-88.5	+70/-80.3	+/-62.9	+70/-80.6	+70/-75.2	+70/-77.7	+70/-71.2	+70/-74.3
	63"	+/-55.7	+/-43.6	+70/-80.7	+70/-89.5	+/-49.3	+70/-77.3	+70/-90	+70/-72.3	+70/-90	+/-66.9	+70/-84.3	+70/-76.5	+/-59.9	+70/-76.5	+70/-71.6	+70/-73.7	+/-67.8	+70/-70.1

TABLE 7:

	Design Pressure (psf) for Windows Attached to a Horizontal Frame Assembly Tube											
	Window Width											
	under 23"	25-15/16"	27-3/4"	30"	33-1/2"		35"			37"		
	Anchor Group	Anchor Group	Anchor Group	Anchor Group	Anchor Group		Anchor Group			Anchor Group		
Window Height	All	All	All	All	B	A, C & D	A	B	C & D	A	B	C & D
	under 23"	+70/-90	+70/-90	+70/-90	+70/-82.1	+70/-90	+70/-90	+70/-78.5	+70/-90	+70/-90	+70/-74.3	+70/-90
	25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-88.8	+70/-90	+70/-90	+70/-84	+70/-90	+70/-90
	38-3/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	48"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	50-5/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-89.2	+70/-89.2	+70/-89.2
	60"	+70/-90	+70/-90	+70/-90	+70/-88.5	+70/-80.6	+70/-80.6	+70/-77.7	+70/-77.7	+70/-77.7	+70/-74.3	+70/-74.3
	63"	+70/-90	+70/-90	+70/-90	+70/-84.3	+70/-76.5	+70/-76.5	+70/-73.7	+70/-73.7	+70/-73.7	+70/-70.1	+70/-70.1
	72"	+70/-90	+70/-87.2	+70/-77.7	+70/-71.5	+60/-62.4	+60/-62.4	+60/-60.9	+60/-60.9	+60/-60.9	+/-59.3	+/-59.3
	76"	+70/-90	+70/-84.6	+70/-75.7	+/-67.3	+/-58.9	+/-58.9	+/-57.2	+/-57.2	+/-57.2	+/-55.6	+/-55.6
	84"	+70/-90	+70/-80.4	+70/-71.3	+60/-62.1	+/-54.2	+/-54.2					



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES. SEE SHEET 3 FOR ANY ADDITIONAL ANCHORS REQUIRED FOR THE FRAME ASSEMBLY TUBE.



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES. SEE SHEET 3 FOR ANY ADDITIONAL ANCHORS REQUIRED FOR THE FRAME ASSEMBLY TUBE.

NOTES:
1) SEE SHEET 4 FOR ADDITIONAL SAMPLE CONFIGURATIONS.
2) SEE SHEET 4 FOR SNUBBER REQUIREMENTS.

Revision A:	NO CHANGE THIS SHEET	Date:	5/15/15	Revised By:	L MILLER
		Date:	08/08/12	Drawn By:	J ROSOWSKI
				Description:	DESIGN PRESSURES PER GLAZING TYPE
				Title:	CASEMENT WINDOW DETAILS - LM & SM
				Series/Model:	CA-740
				Scale:	NTS
				Sheet:	5 OF 10
				Drawing No.:	MD-CA740-LM
				Rev:	A

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
CERT. OF AUTH. #29296





TABLE 8:

		Design Pressure (psf) for Single Windows, All Anchor Groups						
		Window Width						
		under 23"	25-15/16"	27-3/4"	30"	33-1/2"	35"	37"
Window Height	under 23"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	25-15/16"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	38-3/8"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	48"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	50-5/8"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	60"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	63"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-129.6
	72"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-129.1	+90/-122.5	+90/-113.8
	76"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-124.1	+90/-116.7	+90/-107.8
	84"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-116.4		



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES.

FOR GLASS TYPES:

2) 7/16" LAMI (3/16 AN - .090" SG - 3/16 AN)

"SG"= SENTRYGLAS® BY KURARAY AMERICA, INC.


PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0519-13
Expiration Date April 11, 2018
By *[Signature]*
Miami Code Product Control

TABLE 9:


		Design Pressure (psf) for Windows Attached to a Vertical Frame Assembly Tube																			
		Window Width																			
		under 23"				25-15/16"			27-3/4"		30"			33-1/2"			35"		37"		
		Anchor Group				Anchor Group			Anchor Group		Anchor Group			Anchor Group			Anchor Group		Anchor Group		
		A	B	C	D	A	B	C & D	B	A, C & D	A	B	C & D	A	B	C & D	B	A, C & D	A	B	C & D
Window Height	under 23"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	
	25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	
	38-3/8"	+70/-90	+70/-71.6	+70/-90	+70/-90	+70/-81	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	
	48"	+70/-73.1	+/-57.3	+70/-90	+70/-90	+/-84.8	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-87.8	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-88.9	+70/-90
	50-5/8"	+/-69.3	+/-54.3	+70/-90	+70/-90	+/-61.4	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-83.2	+70/-90	+70/-90	+70/-90	+70/-90	+70/-89.2	+70/-90	+70/-90	+70/-84.3	+70/-90
	60"	+/-58.5	+/-45.8	+70/-84.7	+70/-90	+/-51.8	+70/-81.2	+70/-90	+70/-75.9	+70/-90	+70/-89.6	+70/-70.2	+70/-90	+70/-80.3	+70/-78.6	+70/-90	+70/-75.2	+70/-90	+70/-90	+70/-71.2	+70/-90
	63"	+/-55.7	+/-43.6	+70/-80.7	+70/-89.5	+/-49.3	+70/-77.3	+70/-90	+70/-72.3	+70/-90	+70/-85.3	+/-66.9	+70/-90	+70/-76.5	+70/-74.9	+70/-90	+70/-71.6	+70/-90	+70/-86.5	+/-67.8	+70/-90

TABLE 10:

		Design Pressure (psf) for Windows Attached to a Horizontal Frame Assembly Tube											
		Window Width											
		under 23"	25-15/16"	27-3/4"	30"	33-1/2"		35"			37"		
		Anchor Group	Anchor Group	Anchor Group	Anchor Group	Anchor Group	Anchor Group	Anchor Group			Anchor Group		
		All	All	All	All	B	A, C & D	A	B	C & D	A	B	C & D
Window Height		under 23"	+70/-90	+70/-90	+70/-90	+70/-82.1	+70/-90	+70/-90	+70/-78.5	+70/-90	+70/-90	+70/-74.3	+70/-90
	25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-88.8	+70/-90	+70/-90	+70/-84	+70/-90	+70/-90
	38-3/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	48"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	50-5/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	60"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	63"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	72"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	76"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	84"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90						



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES. SEE SHEET 3 FOR ANY ADDITIONAL ANCHORS REQUIRED FOR THE FRAME ASSEMBLY TUBE.



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES. SEE SHEET 3 FOR ANY ADDITIONAL ANCHORS REQUIRED FOR THE FRAME ASSEMBLY TUBE.

NOTES:

- 1) SEE SHEET 4 FOR ADDITIONAL SAMPLE CONFIGURATIONS.
- 2) SEE SHEET 4 FOR SNUBBER REQUIREMENTS.

Revision A: NO CHANGE THIS SHEET

Date: 5/15/15

Revised By: L MILLER

Drawn By: J ROSOWSKI

Description: DESIGN PRESSURES PER GLAZING TYPE

Title: CASEMENT WINDOW DETAILS - LM & SM

Series/Model: CA-740

Scale: NTS

Sheet: 6 OF 10


Drawing No. MD-CA740-LM

Rev: A

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
CERT. OF AUTH. #29295ANTHONY LYNN MILLER
LICENSE
No. 58705
7/10/15
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER P.E.
P.E. # 58705

TABLE 11:

		Design Pressure (psf) for Single Windows, All Anchor Groups						
		Window Width						
		under 23"	25-15/16"	27-3/4"	30"	33-1/2"	35"	37"
Window Height	under 23"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	25-15/16"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	38-3/8"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	48"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	50-5/8"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	60"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	63"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	72"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	76"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130
	84"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130		



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES.

FOR GLASS TYPES:

- 3) 7/16" LAMI (3/16 HS - .090" SG - 3/16 HS)
 7) 7/8" LAMI. IG: (3/16" AN - 1/4" AIR - 3/16" HS - .090" SG - 3/16" HS)
 9) 7/8" LAMI. IG: (3/16" T - 1/4" AIR - 3/16" HS - .090" SG - 3/16" HS)

"SG"= SENTRYGLAS® BY KURARAY AMERICA, INC.

PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No. 15-0519.13
 Expiration Date April 11, 2018
 By *Manuel J. [Signature]*
 Miami/Dade Product Control

TABLE 12:


		Design Pressure (psf) for Windows Attached to a Vertical Frame Assembly Tube																			
		Window Width																			
		under 23"				25-15/16"			27-3/4"		30"			33-1/2"			35"		37"		
		Anchor Group				Anchor Group			Anchor Group		Anchor Group			Anchor Group			Anchor Group		Anchor Group		
		A	B	C	D	A	B	C & D	B	A, C & D	A	B	C & D	A	B	C & D	B	A, C & D	A	B	C & D
Window Height	under 23"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	
	25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	
	38-3/8"	+70/-90	+70/-71.6	+70/-90	+70/-90	+70/-81	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	
	48"	+70/-73.1	+/-57.3	+70/-90	+70/-90	+/-64.8	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-87.8	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-88.9	+70/-90	
	50-5/8"	+/-69.3	+/-54.3	+70/-90	+70/-90	+/-61.4	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-83.2	+70/-90	+70/-90	+70/-90	+70/-89.2	+70/-90	+70/-90	+70/-84.3	+70/-90	
	60"	+/-58.5	+/-45.8	+70/-84.7	+70/-90	+/-51.8	+70/-81.2	+70/-90	+70/-75.9	+70/-90	+70/-89.6	+70/-70.2	+70/-90	+70/-80.3	+70/-78.6	+70/-90	+70/-75.2	+70/-90	+70/-90	+70/-71.2	+70/-90
	63"	+/-55.7	+/-43.6	+70/-80.7	+70/-89.5	+/-49.3	+70/-77.3	+70/-90	+70/-72.3	+70/-90	+70/-85.3	+/-66.9	+70/-90	+70/-76.5	+70/-74.9	+70/-90	+70/-71.6	+70/-90	+70/-86.5	+/-67.8	+70/-90

TABLE 13:


		Design Pressure (psf) for Windows Attached to a Horizontal Frame Assembly Tube											
		Window Width											
		under 23"	25-15/16"	27-3/4"	30"	33-1/2"		35"			37"		
		Anchor Group	Anchor Group	Anchor Group	Anchor Group	Anchor Group	Anchor Group	Anchor Group			Anchor Group		
		All	All	All	All	B	A, C & D	A	B	C & D	A	B	C & D
Window Height	under 23"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-82.1	+70/-90	+70/-90	+70/-78.5	+70/-90	+70/-90	+70/-74.3	+70/-90
	25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-88.8	+70/-90	+70/-90	+70/-84	+70/-90	+70/-90
	38-3/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	48"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	50-5/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	60"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	63"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	72"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	76"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	84"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90						

NOTES:

- 1) SEE SHEET 4 FOR ADDITIONAL SAMPLE CONFIGURATIONS.
 2) SEE SHEET 4 FOR SNUBBER REQUIREMENTS.




SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES. SEE SHEET 3 FOR ANY ADDITIONAL ANCHORS REQUIRED FOR THE FRAME ASSEMBLY TUBE.



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES. SEE SHEET 3 FOR ANY ADDITIONAL ANCHORS REQUIRED FOR THE FRAME ASSEMBLY TUBE.

Revised By:	Date:	Revised By:	Date:	Description:	Title:	Series/Model:	Scale:	Sheet:	Revision:
L MILLER	5/15/15	J ROSOWSKI	08/08/12	DESIGN PRESSURES PER GLAZING TYPE	CASEMENT WINDOW DETAILS - LM & SM	CA-740	NTS	7 OF 10	MD-CA740-LM A



1070 TECHNOLOGY DRIVE
 N. VENICE, FL 34275
 P.O. BOX 1529
 NOKOMIS, FL 34274
 CERT. OF AUTH. #29296





TABLE 14:

		Design Pressure (psf) for Single Windows, All Anchor Groups						
		Window Width						
		under 23"	25-15/16"	27-3/4"	30"	33-1/2"	35"	37"
Window Height	under 23"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	38-3/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	48"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	50-5/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	60"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-88.6	+70/-84.6
	63"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-87.2	+70/-84	+70/-79.9
	72"	+70/-90	+70/-90	+70/-88.5	+70/-81.5	+60/-70	+60/-69.4	+60/-67.6
	76"	+70/-90	+70/-90	+70/-86.3	+70/-76.7	+60/-67.2	+60/-65.2	+60/-63.3
	84"	+70/-90	+70/-90	+70/-81.3	+60/-70	+60/-61.8		



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES.

FOR GLASS TYPES:

5) 7/8" LAMI. IG: (1/8" T - 7/16" AIR - 1/8" AN - .090" PVB - 1/8" AN)

PVB= BUTACITE® PVB BY KURARAY AMERICA, INC.


PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0519.13
Expiration Date April 11, 2018
By *Manuel Perez*
Miami/Dade Product Control

TABLE 15:


		Design Pressure (psf) for Windows Attached to a Vertical Frame Assembly Tube																	
		Window Width																	
		under 23"				25-15/16"			27-3/4"		30"			33-1/2"			35"		37"
		Anchor Group				Anchor Group			Anchor Group		Anchor Group			Anchor Group			Anchor Group		Anchor Group
		A	B	C	D	A	B	C & D	B	A, C & D	A	B	C & D	A	B	C & D	B	A, C & D	B, A, C & D
Window Height	under 23"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	38-3/8"	+70/-90	+70/-71.6	+70/-90	+70/-90	+70/-81	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	48"	+70/-73.1	+/-57.3	+70/-90	+70/-90	+/-84.8	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-87.8	+70/-90	+70/-90	+70/-78.6	+70/-90	+70/-90	+70/-88.9	+70/-90
	50-5/8"	+/-69.3	+/-54.3	+70/-90	+70/-90	+/-61.4	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-83.2	+70/-90	+70/-90	+70/-74.6	+70/-90	+70/-89.2	+70/-84.3	+70/-90
	60"	+/-58.5	+/-45.8	+70/-84.7	+70/-90	+/-51.8	+70/-81.2	+70/-90	+70/-75.9	+70/-90	+70/-89.6	+70/-70.2	+70/-90	+70/-80.3	+/-62.9	+70/-90	+70/-75.2	+70/-88.6	+70/-84.6
	63"	+/-55.7	+/-43.6	+70/-80.7	+70/-89.5	+/-49.3	+70/-77.3	+70/-90	+70/-72.3	+70/-90	+70/-85.3	+/-66.9	+70/-90	+70/-76.5	+/-59.9	+70/-87.2	+70/-71.6	+70/-84	+/-67.8

TABLE 16:

		Design Pressure (psf) for Windows Attached to a Horizontal Frame Assembly Tube											
		Window Width											
		under 23"	25-15/16"	27-3/4"	30"	33-1/2"		35"			37"		
		Anchor Group	Anchor Group	Anchor Group	Anchor Group	Anchor Group		Anchor Group			Anchor Group		
		All	All	All	All	B	A, C & D	A	B	C & D	A	B	C & D
Window Height	under 23"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-82.1	+70/-90	+70/-90	+70/-78.5	+70/-90	+70/-90	+70/-74.3	+70/-90
	25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-88.8	+70/-90	+70/-90	+70/-84	+70/-90	+70/-90
	38-3/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	48"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	50-5/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
	60"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-88.6	+70/-88.6	+70/-88.6	+70/-84.6	+70/-84.6	+70/-84.6
	63"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-87.2	+70/-87.2	+70/-84	+70/-84	+70/-84	+70/-79.9	+70/-79.9	+70/-79.9
	72"	+70/-90	+70/-90	+70/-88.5	+70/-81.5	+60/-70	+60/-70	+60/-69.4	+60/-69.4	+60/-69.4	+60/-67.6	+60/-67.6	+60/-67.6
	76"	+70/-90	+70/-90	+70/-86.3	+70/-76.7	+60/-67.2	+60/-67.2	+60/-65.2	+60/-65.2	+60/-65.2	+60/-63.3	+60/-63.3	+60/-63.3
	84"	+70/-90	+70/-90	+70/-81.3	+60/-70	+60/-61.8	+60/-61.8						




SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES. SEE SHEET 3 FOR ANY ADDITIONAL ANCHORS REQUIRED FOR THE FRAME ASSEMBLY TUBE.



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES. SEE SHEET 3 FOR ANY ADDITIONAL ANCHORS REQUIRED FOR THE FRAME ASSEMBLY TUBE.

NOTES:
1) SEE SHEET 4 FOR ADDITIONAL SAMPLE CONFIGURATIONS.
2) SEE SHEET 4 FOR SNUBBER REQUIREMENTS.

Revision A: NO CHANGE THIS SHEET
Date: 5/15/15
Revised By: L MILLER
Drawn By: J ROSOWSKI
Date: 08/08/12
Description: DESIGN PRESSURES PER GLAZING TYPE
Title: CASEMENT WINDOW DETAILS - LM & SM
Series/Model: CA-740
Scale: NTS
Sheet: 8 OF 10
Drawing No. MD-CA740-LM
Rev: A



1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
CERT. OF AUTH. #29296





TABLE 17:

Window Height	Design Pressure (psf) for Single Windows, All Anchor Groups							
	Window Width							
	under 23"	25-15/16"	27-3/4"	30"	33-1/2"	35"	37"	
under 23"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	
25-15/16"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	
38-3/8"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	
48"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	
50-5/8"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	
60"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	
63"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	
72"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-130	+90/-124.6	+90/-115.7	
76"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-126.2	+90/-118.7	+90/-109.6	
84"	+90/-130	+90/-130	+90/-130	+90/-130	+90/-118.4			



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES.

FOR GLASS TYPES:

- 6) 7/8" LAMI. IG: (3/16" AN - 1/4" AIR - 3/16" AN - .090" SG - 3/16" AN)
 8) 7/8" LAMI. IG: (3/16" T - 1/4" AIR - 3/16" AN - .090" SG - 3/16" AN)

"SG"= SENTRYGLAS® BY KURARAY AMERICA, INC.

PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No. 15-0519.13
 Expiration Date April 11, 2018
 By *M. Miller*
 Miami Dade Product Control

TABLE 18:


Window Height	Design Pressure (psf) for Windows Attached to a Vertical Frame Assembly Tube																				
	Window Width																				
	under 23"				25-15/16"			27-3/4"		30"			33-1/2"			35"		37"			
	Anchor Group				Anchor Group			Anchor Group		Anchor Group			Anchor Group			Anchor Group		Anchor Group			
	A	B	C	D	A	B	C & D	B	A, C & D	A	B	C & D	A	B	C & D	B	A, C & D	A	B	C & D	
under 23"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	
25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	
38-3/8"	+70/-90	+70/-71.6	+70/-90	+70/-90	+70/-81	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	
48"	+70/-73.1	+/-57.3	+70/-90	+70/-90	+/-64.8	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-87.8	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	
50-5/8"	+/-69.3	+/-54.3	+70/-90	+70/-90	+/-61.4	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-83.2	+70/-90	+70/-90	+70/-90	+70/-90	+70/-89.2	+70/-90	+70/-90	+70/-90	+70/-90	
60"	+/-58.5	+/-45.8	+70/-84.7	+70/-90	+/-51.8	+70/-81.2	+70/-90	+70/-75.9	+70/-90	+70/-89.6	+70/-70.2	+70/-90	+70/-80.3	+70/-78.6	+70/-90	+70/-75.2	+70/-90	+70/-90	+70/-90	+70/-90	
63"	+/-55.7	+/-43.6	+70/-80.7	+70/-89.5	+/-49.3	+70/-77.3	+70/-90	+70/-72.3	+70/-90	+70/-85.3	+/-66.9	+70/-90	+70/-76.5	+70/-74.9	+70/-90	+70/-71.6	+70/-90	+70/-86.5	+/-67.8	+70/-90	

TABLE 19:


Window Height	Design Pressure (psf) for Windows Attached to a Horizontal Frame Assembly Tube											
	Window Width											
	under 23"	25-15/16"	27-3/4"	30"	33-1/2"		35"			37"		
	Anchor Group	Anchor Group	Anchor Group	Anchor Group	Anchor Group	Anchor Group	Anchor Group			Anchor Group		
	All	All	All	All	B	A, C & D	A	B	C & D	A	B	C & D
under 23"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-82.1	+70/-90	+70/-90	+70/-78.5	+70/-90	+70/-90	+70/-74.3	+70/-90
25-15/16"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-88.8	+70/-90	+70/-90	+70/-84	+70/-90	+70/-90
38-3/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
48"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
50-5/8"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
60"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
63"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
72"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
76"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90
84"	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90	+70/-90						

NOTES:

- 1) SEE SHEET 4 FOR ADDITIONAL SAMPLE CONFIGURATIONS.
 2) SEE SHEET 4 FOR SNUBBER REQUIREMENTS.



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES. SEE SHEET 3 FOR ANY ADDITIONAL ANCHORS REQUIRED FOR THE FRAME ASSEMBLY TUBE.



SEE SHEETS 1 & 4 FOR WINDOW ANCHOR LOCATIONS AND QUANTITIES. SEE SHEET 3 FOR ANY ADDITIONAL ANCHORS REQUIRED FOR THE FRAME ASSEMBLY TUBE.

Revised By:	L MILLER	Date:	5/15/15	Revision A:	NO CHANGE THIS SHEET
Drawn By:	J ROSOWSKI	Date:	08/08/12		
Description:	DESIGN PRESSURES PER GLAZING TYPE				
Title:	CASEMENT WINDOW DETAILS - LM & SM				
Series/Model:	CA-740	Scale:	NTS	Sheet:	9 OF 10
				Drawing No.	MD-CA740-LM
				Rev:	A





TABLE 20:




Item	Dwg. #	Description	Material
1	7002	Main Frame Head, Sill & Jamb	6063-T6 Alum.
2	7071	Anchor Plate	6063-T6 Alum.
3	7003	Sash Top, Bottom & Side Rail	6063-T6 Alum.
4	7008	Frame Corner Key	Steel
5	7009	Sash Corner Key	Steel
6	7078	Frame Gasket	Vinyl Foam
7	7072	Sash Corner Gasket	Vinyl Foam
8	7070	Bulb Weatherstrip .187" x .275"	Flex PVC 70
10	7024	Maxim Multi-Point Lock	Steel
11	7026	Lock Support Plate	Steel
12	7014	Multi-Lock Keeper	Steel
13	7013	Tie Bar Guide	Nylon
14	7015	Tie Bar Assembly	Steel or SS
15	7028	Maxim Dyad Operator, WW<=24"	Steel
16	7027	Maxim Dual Arm Operator, WW>24"	Steel
17	7030	Operator Gasket	Vinyl Foam
18	7031	Operator Backing Plate	Steel
19	7051	Operator Spacer Block	Nylon
20	7032	Stud Bracket	Steel
21	7033	Operator Track & Slider (Dual Arm)	Steel
22	7023	Egress Hinge (Heavy Duty), Manuf. by Truth	Steel
23	7050	Egress Hinge/Washable (HD), Manuf. by Truth	Steel
24		Snubber, Anti-blowout Clip	Steel
31		Dura Seal Spacer	Steel
32	1713	Setting Block 5/32" x 3/16" x 1-1/4"	EPDM
33	1714	Setting Block 5/32" x 7/16" x 1-1/4"	EPDM
35	7036	Lami Bead B	6063-T6 Alum.
36	7042	Lami Bead C	6063-T6 Alum.
37	7059	Lami Bead D	6063-T6 Alum.
38	1224	Vinyl Bulb Wstp (Thick)	Flex PVC 70
39	1225	Vinyl Bulb Wstp (Thin)	Flex PVC 70
50		Dow 899 Silicon Backbedding	
60	7006	Screen Frame	3105-H14 Alum.
61	7040	Screen Corner Key	Polypropylene
62		Screen Cloth	Fiberglass
63	1635	Screen Spline	EM. PVC
64	320	Screen Spring	Stainless Steel
70	134	Add-on Flange	6063-T6 Alum.
71	7004	Frame Assy Tube	6063-T6 Alum.
80		#8-32 x 1/2" Ph. Pn. Mach. Scr TYPE B	Stainless Steel
81	1157	#8 x 1/2" Ph. Pn. SMS	Stainless Steel
82		#8 x 5/8" Fl. Ph. SMS	Stainless Steel
83		#8 x 7/8" Fl. Ph. SMS	Stainless Steel
84		#8 x 1" Fl. Ph. TEK	Stainless Steel
85		#8 x 1" Quad Pn SMS	Stainless Steel
86		#8 X 1-1/2" Quad Pn SMS	Stainless Steel
87		#10 x 1/2" Ph. Pn./ TEK	Stainless Steel
89		#10-24 x 9/16" Ph. Pn. TYPE F	Stainless Steel
90		#12 x 1" Ph. Pn. TEK	Stainless Steel

ASSEMBLY DETAILS

ALL DETAILS SHOWN FROM THE INTERIOR

AS REQUIRED PER
TABLE 3, SHEET 4SASH
CORNERSFRAME
CORNERS

INTERIOR

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274

CERT. OF AUTH. #29296

Revised By:	Date:	Revision B:
Revised By:	Date:	Revision A:
LM	5/15/15	NO CHANGE THIS SHEET
Description: BOM AND CORNER VIEWS		Drawn By: J ROSOWSKI
Title: CASEMENT WINDOW DETAILS - LM & SM		Date: 08/08/12
Series/Model: CA-740	Scale: NTS	Sheet: 10 OF 10
Drawing No. MD-CA740-LM		Rev: A

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 15-0519.13
Expiration Date April 11, 2018
By *Manuel Perez*
Miami Dade Product Control